DGS
GENERAL SERVICES

State of California
Department of General Services
Real Estate Services Division

ACCESSIBILITY CHECKLIST

FOR STATE-LEASED BUILDINGS AND FACILITIES

DEPARTMENT OF REHABILITION

4930 W KAWEAH COURT SUITE 100 VISALIA, CA 93277

RESD PROJECT #139602

T·A·B·A
ARCHITECTURE
T A BLUHM ASSOCIATES

4539 N BRAWLEY AVE SUITE 101
FRESNO, CA
559.276.7711

ACCESSIBILITY CHECKLIST
FOR STATE-LEASED BUILDINGS AND FACILITIES

The purpose of this accessibility checklist is to enable trained accessibility experts and design professionals to efficiently evaluate state-leased, rented, contracted, or sublet facilities for compliance with accessibility requirements of the 2013 California Building Code (CBC). It is not intended to be an exhaustive list of all the architectural barriers that can occur at a facility; however, it is a list of common architectural barriers which may exist at such facilities. For additional information on a particular code item, consult the CBC for more detailed information. Therefore, it is the responsibility of the surveyor to document on additional sheets any details or deviations that are identified during the survey.

REQUIREMENTS FOR LEASES AND LEASE RENEWALS

These survey sheets document the accessibility status of the portions of the site and facility that provide access to and use of newly leased or lease-renewed space for State of California agencies, hereinafter called the "Primary Area". It is not intended to include other areas of the site and facility that do not provide access to and use of newly leased or lease-renewed space.

Elements to be evaluated include, but are not limited to, routes of travel from/to public transportation (if adjacent to the property line), routes of travel from/to the public right-of-way, parking, passenger drop-off and loading zones, walks and sidewalks, curb ramps, ramps, entrances and exits, horizontal/vertical access, lobbies, elevators, platform (wheelchair) lifts, doors and gates, toilet rooms, signage, counters, waiting and seating areas, public telephones, drinking fountains, alarms, assistive listening systems, and access to and through all rooms and spaces which serve the Primary Area.

If the Primary Area or public and common use areas serving the Primary Area are located on a level other than the ground floor level, an accessible elevator must provide access to that level. Note that the use of platform (wheelchair) lifts to provide accessibility is very limited in state-leased facilities.

Common and public use stairways directly serving the Primary Area must be surveyed, as well as those flights of emergency egress stairways that provide access between a Primary Area that is spread over two or more floors (communication stairways). Stairs used solely for emergency egress must meet current California Building Code. Doorways (including signage) leading to such emergency stairways must be surveyed if they serve the Primary Area or any common use areas serving the Primary Area.

The surveyor shall include all public and common use areas such as lobbies, elevators, stairways, corridors, toilet rooms, meeting and conference rooms, etc., that are not within but serve the Primary Area. Public and common use areas that do not serve state-leased space do not require surveying.

State agencies are public entities and shall comply with Title II of the ADA. Exceptions to the code for existing buildings are not permitted. The 2013 CBC was reorganized to use the format and organization of the ADA Standards; therefore, the ADA Standard references have been removed from the checklist and the CBC is the code reference. The surveyor still has the responsibility to verify any conflicts or differences between the CBC and the ADA. Where there are conflicts or differences, the most stringent shall take precedence.

For special provisions at state-leased facilities in qualified historical buildings see CBC 11B-202.5.

SURVEY INSTRUCTIONS

Checklists that do not conform to this format and content are <u>not acceptable</u>.

This checklist is designed to be used in full or in part, depending on the type of facility and specific elements provided. For example, if no drinking fountains are provided at a facility, the Survey Form for drinking fountains does not have to be completed.

Fill-in the facility name and RESD project (ABMS) number on each Summary Sheet and Survey Form. Each Survey Form has a title block used to identify the specific element being inspecting. Each survey question has one or more CBC references. If you do not understand the question, look up the specific reference(s) in the CBC.

Questions are asked in a "yes/no" format. Each item must be checked either “yes”, “no”, or “N/A” (not applicable). Do not leave blank boxes; if the specific element does not exist, check "N/A".

Important: If a certain requirement is not met, indicate as precisely as possible, the existing condition in the comments column, for example, "clear opening width only 29 inches”, "handrail diameter 4 inches”, or "ramp slope 1:10”. This information will assist those using the survey at a later date to remove identified barriers. Use the comment column or attach additional sheets containing sketches, plans or photos to describe non-typical situations.

Contact the building management to advise them that a survey will be conducted, and ask if site and floor plans are available for the facility. A plan can be helpful, particularly if surveying a large facility. Key numbers can be assigned to areas or specific elements on the plan and then be used to correlate the Survey Forms. It is estimated that a site inspection will take between two and six hours, depending on the size of the facility.

Step 1: Identify the Type of Facility or Building Use
Complete the General Facility and Survey Information Data Sheet to document the name and address of the facility, RESD project number, dates of construction and alteration, type of facility or building use, number of stories and size of each, name of surveyor and date of survey.

Step 2: Determine Minimum Requirements
The minimum requirements Summary Sheets describe which elements are required to be accessible, such as a toilet room or an accessible route of travel between the entrance and parking. Use the Summary Sheets to identify the specific elements of the facility which must be accessible.

Take a quick tour of the facility and/or look at the building plans, and complete each Summary Sheet in the order in which it is presented. The Summary Sheets will ask for an inventory of the specific facility elements which must be accessible.

The principle of an "accessible route" is key to the Summary Sheets. An "accessible route" is simply a route of travel a person in a wheelchair or someone with a mobility limitation would find safe and easy to use. (See definitions in 11B-206). The Summary Sheets define where these accessible routes must be.

Step 3: Copy and Assemble the Survey Forms
Return to your workplace with the completed Summary Sheets. Use the completed Summary Sheets to determine how many copies are needed of each technical requirement Survey Form. Some forms will be needed more than once, while others will not be needed at all. Some forms will reference other forms. Two forms that are referenced quite frequently are Form 11 - Doors and Gates and Form 12 - Building Lobbies and Corridors. Where forms are cross-referenced, a copy of the form will be needed for reference.

In some multi-story buildings, certain accessible elements may be duplicated, and a "shorthand" method of surveying these elements can be developed. For instance, accessible drinking fountains may be installed in the same location in a corridor on the first through the tenth floor of a ten-story building. It may be sufficient to use only one form (Form 5 - Drinking Fountains) to assess compliance in detail for a typical drinking fountain on the first floor, and then note that each drinking fountain on the second through the tenth floor is the same. All elevators are required to be accessible, but where there are three elevators in a bank, all three elevators may be the same. A single form (Form 13 - Elevators) to survey all three elevators in the same bank may be sufficient.

Copy the necessary Survey Forms and attach them to the Summary Sheet which called for them. When complete, the survey package will contain a series of technical requirements Survey Forms divided by the minimum requirements Summary Sheets, which progress logically through the facility. Cover the entire package with the General Facility and Survey Information Data Sheet.

Step 4: Survey
In addition to the survey package (Summary Sheets and Survey Forms), the following equipment is needed for the survey:

- Copy of CBC Chapter 11B
- Clipboard or binder and extra paper
- Pencil and eraser
- Flexible measuring tape (20 ft minimum)
- Smart level (24-inch) to measure slopes, calibrated
- Contracted (Grade 2) Braille spacing template
- Fish scale or pressure gauge to measure door opening forces
- Camera
- Caliper to accurately measure grab bar and handrail dimensions

Abbreviations used in the checklist:

CBC – California Building Code (2013)

ADA – The American with Disabilities Act

AFF – Above Finished Floor

CL – Centerline

Ft or ' – feet

In or " – inch

lbs – pounds

ISA – International Symbol of Accessibility

o.c. – On Center

SF – Square Feet

TABLE OF CONTENT

General Facility And Survey Information

Minimum Requirements Summary Sheets

Sheet A: Parking (PK)
Sheet B: Passenger Loading Zones (PZ)
Sheet C: Exterior Routes Of Travel (EP)
Sheet D: Entrances (EN)
Sheet E: Interior Routes of Travel (IP)
Sheet F: Rooms and Spaces (RS)
Sheet G: Toilet Rooms (TR)
Sheet H: Assembly Use Areas (AA)
Sheet I: Alarms (AL)
Sheet J: Hazards (HZ)

Technical Requirements Survey Forms

Form 1: Parking
Form 2: Passenger Loading Zones
Form 3A: Exterior Routes of Travel, Public Rights-of-Way (ROW)
Form 3B: Exterior Routes of Travel, On-Site (OS)
Form 4: Curb Ramps
Form 5: Drinking Fountains
Form 6: Telephones
Form 7: Ramps
Form 8: Stairs
Form 9: Platform Lifts
Form 10: Building Entrances and Exits
Form 11: Doors and Gates
Form 12A: Building Lobbies and Corridors (Interior Accessible Route)
Form 12B: State Agency Lobbies and Reception Areas
Form 13: Elevators
Form 14: Rooms and Spaces
Form 15A: Assembly Use Areas, Large Assembly Rooms
Form 15B: Assembly Use Areas, Conference and Meeting Rooms (<750 sf)
Form 16: Toilet Rooms
Form 17: Shower Facility
Form 18: Reserved
Form 19: Signage
Form 20: Alarms
Form 21: Reserved
Form 22: Reserved

GENERAL FACILITY AND SURVEY INFORMATION — Data Sheet

Facility Name: DEPARTMENT OF REHABILITATION

RESD Project No.: 139602

(Type or print. Circle where applicable. Use additional sheets if necessary)

a.	Facility Name	DEPARTMENT OF REHABILITATION			
b.	Facility Address (No., Street)	4350 W KAWEAH COURT SUITE 100			
c.	Facility Address (City, Zip)	VISALIA, 93277			
d.	Landlord Contact Info	VISALIA UNIFIED SCHOOL DISTRICT – C/O MANCO ABBOTT REAL ESTATE MANAGEMENT ATTN: ERIN SPENCER – 559.435.1756			
e.	RESD File No. and RESD Project No.	3576-002		139602	
f.	RESD Project Planner Contact Info	TERRY YU Terry.yu@dgs.ca.gov PHONE: 916.375.4119 FAX: 916.376.6382			
g.	Number of On-site Parking Stalls	+/-99 +/-84 OPEN STALLS & +/-15 COVERED STALLS			
h.	Leased Space Square Footage	4,133 SF			
i.	No. of Stories and Size of Each (Leased Space only)	1			
j.	Date of Construction (First Certificate of Occupancy)	1991			
k.	Date(s) and Type(s) of Previous Alteration(s)	N/A			
l.	Circle or Mark Type of Lease	New Lease	Lease Renewal	Purchase Option	Other (specify)
m.	Tenant Contact Info (Department/Agency)	DEPARTMENT OF REHABILITATION			
n.	Suite No(s) and Size of Each (SF)	SUITE 100 4,133 SF			
o.	Name of Surveyor and Date of Survey	Name: MICHAEL BLUHM			Date: 2.5.16
p.	Surveyor Contact Info	4539 N BRAWLEY AVENUE SUITE 101, FRESNO, CA 93722 Mike@CASpinspected.com PHONE: 559.276.7711 FAX: 559.276.7113			
q.	Surveyor Qualification and License No.	ICC Cert. #	CASp #223	Architect #	
r.	Signature of Surveyor and Date	Signature:			Date: 2.5.16

s.	Attached Summary Sheets (Circle or Mark)	A	B	C	D	E	F1	F2	G	H	I	J

Additional Comments:

Facility
Name: DEPARTMENT OF REHABILITATION

RESD
Project No.: 139602

Parking:
Where self parking is provided for employees or visitors, each parking area/lot or structure is required to have accessible parking spaces complying with the following table and with CBC 11B-208.2.

Total parking in area/lot or structure	Required minimum number of accessible spaces (including van)
1 to 25	1
26 to 50	2
51 to 75	3
76 to 100	4
101 to 150	5
151 to 200	6
201 to 300	7
301 to 400	8
401 to 500	9
501 to 1000	2 percent of total
1001 and over	20 plus 1 for each 100 over 1000
At outpatient units and facilities	10 percent
At facilities specializing in treatment for persons with mobility impairments	20 percent

Note: Spaces required by the table need not be provided in the particular area/lot or structure. They may be provided at a different location if equivalent or greater accessibility, in terms of distance from an accessible entrance, user cost and convenience, is ensured.

In addition, one in every six accessible spaces, but not less than one, must be a van accessible space. Car and van parking spaces shall be 18' long minimum. Car parking spaces shall be 9' wide minimum and van parking spaces shall be 12' wide minimum, and shall have an adjacent access aisle minimum of 5' wide and complying with 11B-502.3. Van parking spaces shall be permitted to be 9' wide minimum where the access aisle is 8' wide minimum and must be designated "Van Accessible". See 11B-502.2.

List all parking areas/lots in the following table and survey each of these lots/structures with a separate copy of Survey Form 1 - Parking. If you encounter curb ramps, ramps, or detectable warnings, survey that element with its specific form. For parking structures which have doors or gates, elevators, public telephones, or drinking fountains survey that element with its specific form.

ID	Name/location of parking lots surveyed (or key number on site plan)	Total parking in lot	Total accessible* provided	Total van accessible provided	Minimum required accessible*	Minimum required van accessible
PK1	OPEN PARKING FRONT	47	2	1	2	1
PK2	OPEN PARKING REAR	37	1	1	2	1
PK3	COVERED PARKING	15	0	0	1	1
PK4						

* Including van accessible spaces

*Indicate the number of Survey Forms attached to Summary Sheet A in the **No**. field.*

Form	Item	No.		Form	Item	No.		Form	Item	No.
SF1	Parking	3		SF4	Curb Ramps	2		SF5	Drinking Fountains	
SF6	Telephones			SF7	Ramps			SF11	Doors and Gates	
SF13	Elevators			SF21	Hazards			SF3B	Exterior RoT (On-site)	1

PARKING

Survey Form 1

Space/Room Item Name: OPEN PARKING FRONT (PK1)	Item No.:	Floor No.:	Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
1.1	Off-site Parking Spaces	If no on-site parking is provided, is there accessible parking provided off-site nearby? (Note: Accessible parking for employees or visitors or both may be provided either in the public rights-of-way or in an off-site facility.) 11B-208.1, 11B-208.3.1			Yes ☐ No ☐ N/A ■
1.2	Number - Accessible Parking Spaces	Where parking spaces are provided for self-parking by employees or visitors or both, is the required number of accessible parking spaces provided? (See Minimum Requirements Summary Sheet A) (Note: All or some of the accessible parking spaces may be in a different location if equivalent or greater accessibility is ensured.) 11B-208.2, Table 11B-208.2			Yes ■ No ☐ N/A ☐
1.3	Each Area/Lot	Are the accessible parking spaces located in each specific area/lot? OR If the accessible parking spaces are in a different location, is equivalent or greater accessibility provided in terms of distance from the accessible entrance, user cost and convenience? 11B-208.2			Yes ■ No ☐ N/A ☐
1.4	Van Accessible Spaces	Is one in every six accessible parking spaces (but not less than one) designated "van accessible"? 11B-208.2.4, 11B-208.2			Yes ■ No ☐ N/A ☐
1.5	Location - Serving Accessible Entrance	Are accessible parking spaces which serve a particular building on the shortest accessible route of travel from adjacent parking to the building's accessible entrance? 11B-208.1, 11B-208.3			Yes ■ No ☐ N/A ☐
1.6	Lot Layout	Are parking stalls arranged so that persons with disabilities are not compelled to wheel or walk behind parked cars other than their own? 11B-502.7.1			Yes ■ No ☐ N/A ☐
1.7	Serving Multiple Accessible Entrances	If the building has multiple accessible entrances with adjacent parking, are the accessible parking spaces dispersed and on the shortest accessible route of travel to the parking facility's accessible pedestrian entrance? 11B-208.1, 11B-208.3.1	PARKING SPACES SERVE THE MAIN FRONT ENTRANCE		Yes ☐ No ☐ N/A ■
1.8	Separate Parking Facility	Where a parking facility does not serve a particular building, are the accessible parking spaces on the shortest accessible route of travel to the parking facility's accessible pedestrian entrance? 11B-208.1, 11B-208.3.1			Yes ☐ No ☐ N/A ■
1.9	Parking Space Width - Car	Are accessible car parking spaces, at least 9' wide and 18' long with a demarcated access aisle? (two spaces may share a common aisle)	PARKING SPACES & ACCESS AISLES ARE 17' LONG		Yes ☐ No ■ N/A ☐
1.10	Parking Space Width - Van	Are accessible van parking spaces at least 12' wide and 18' long with a demarcated access aisle?	17' LONG		Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

PARKING

Survey Form 1

Space/Room Item Name: OPEN PARKING FRONT (PK1)	Item No.:	Floor No.:	Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
1.11	Van Access Aisle	If the parking space is designated as "van accessible," is the adjacent access aisle at least 5' wide by 18' long and located on the passenger side of the vehicle space? See 1.12 below for van space and access aisle size exception. 11B-502.2 exception	17' LONG		Yes ☐ No ■ N/A ☐
1.12	Car & Van Access Parking	If there is a 5' access aisle shared by a car and van, is the car parking space 9' wide and the van parking space 12' wide with 18' long minimum spaces or if the van parking space is 9' wide, is the access aisle 8' wide with 18' long minimum spaces? 11B-502.2	17' LONG		Yes ☐ No ■ N/A ☐
1.13	Car Access Aisles	Are all other access aisles at least 5' wide and 18' long, extending the full required length of the parking space they serve? 11B-502.3.1, 11B-502.3.2	17' LONG		Yes ☐ No ■ N/A ☐
1.14	Level Surface	Are the accessible parking spaces and access aisles level with no slope greater than 1:48 in all directions? (This means a curb ramp cannot project into the access aisle.) 11B-502.4	3.0%-3.8% @ SOUTH 2.5%-3.0% @ NORTH		Yes ☐ No ■ N/A ☐
1.15	Surface	Are access aisles stable, firm, and slip resistant and clear of the vehicular way? 11B-302, 11B-502.3.4			Yes ■ No ☐ N/A ☐
1.16	Access Aisle and Accessible Route	Does each access aisle connect directly to an accessible route of travel, and on the shortest accessible route? (Use Form 3 - Exterior Routes of Travel) 11B-208.3.1	SEE SURVEY FORM FOR ROUTE ISSUES		Yes ■ No ☐ N/A ☐
1.17	Parking Signs	Does each accessible parking space have a reflectorized sign visible from each stall showing the ISA? 11B-502.6			Yes ■ No ☐ N/A ☐
1.18	Car & Van Accessible Parking Signs	Do van accessible spaces have a sign stating "Van Accessible" below the ISA and do both car and van have additional language or an additional sign below the ISA stating "Minimum fine $250" and is it minimum 60" minimum AFF or ground? 11B-502.6, 11B-502.6.2	THERE ARE NO "MINIMUM FINE $250" SIGNS PROVIDED		Yes ☐ No ■ N/A ☐
1.19	Pavement Sign	Is there a minimum 36" square ISA painted on the pavement at the rear of the stall, centered a maximum of 6" from the centerline of the parking space and aligned with the end of the parking space length? 11B-502.6.4.1, 11B-502.6.4.2			Yes ■ No ☐ N/A ☐
1.20	Marking	Is the access aisle marked with a blue painted borderline around the perimeter and marked with hatched lines a maximum of 36' OC in a color contrasting with the aisle surface and are the words "NO PARKING" provided in each access aisle, painted in white, 12" high letters? 11B-502.3.3	NO "NO PARKING" @ SOUTH PARKING SPACE ACCESS AISLE		Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
1.21	Tow-away Sign	Is there a tow-away sign posted in a conspicuous place at each entrance to off–street parking lot, or immediately adjacent to and visible from each accessible stall? 11B-502.8	SIGN @ ONLY (1) OF (3) ENTRANCES & SIGN IS @ GOOD		Yes ☐ No ■ N/A ☐
1.22	Van Accessible Spaces - Vertical Clearance	Do accessible spaces and their access aisles have a vertical clearance of at least 98"? 11B-502.5			Yes ■ No ☐ N/A ☐
1.23	Van Accessible Spaces - Vertical Clearance	Does one vehicular access route to and from van accessible spaces have a vertical clearance of at least 98"? (Van accessible spaces may be grouped on one level of a parking structure.) 11B-502.5			Yes ■ No ☐ N/A ☐
1.24	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room Item Name:	ID No.:	Floor No.:	Project No.:
ROUTE TO/FROM (PKI) TO/FROM ENTRY/EXIT WALKWAY			139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.1B	On-site Accessible Route of Travel	Is there an accessible route of travel within the property line of the site linking an accessible building entrance with site arrival points serving the following, if provided: public transportation stops, passenger loading zones, accessible parking, and public sidewalks? 11B-206.2.1, 11B-402	ROUTE SERVING (PKI) HAS CHANGES IN LEVEL THAT EXCEED 1/4"		Yes ☐ No ■ N/A ☐
3.2B	Route for General Public	Does the accessible route of travel, to the maximum extent feasible, coincide with the route for the general public? 11B-206, 11B-402			Yes ■ No ☐ N/A ☐
3.3B	Facilities Connected	Are there accessible routes of travel connecting all accessible buildings, facilities, elements and spaces on the same site with one another? 11B-206.2.2, 11B-402			Yes ☐ No ☐ N/A ■
3.4B	Width	Is the accessible route of travel at least 48" wide? The clear width can be reduced to 32" minimum for a length of 24" maximum provided that reduced width segments are separated by segments that are 48" long minimum and 36" wide minimum? 11B-302.1, 11B-403.5.1, Exception1, 3	36" WIDE @ CONCRETE APRON BTWN PARKING SPACES		Yes ☐ No ■ N/A ☐
3.5B	Passing Spaces	If the accessible route of travel is less than 60" wide, are there passing spaces at least 60" by 60" or intersecting walks provided, allowing passing at reasonable intervals not exceeding 200'? 11B-403.5.3			Yes ☐ No ☐ N/A ■
3.6B	Head Room	Is there at least 80" clear head room within the pedestrian circulation area, including the accessible route of travel? If the vertical clearance is less than 80" high, is a guardrail or other barrier provided? 11B-307.4			Yes ■ No ☐ N/A ☐
3.7B	Protruding Objects	If wall-mounted objects have leading edges between 27" and 80" from the floor, do they project less than 4" into the circulation path (objects with leading edges at or below 27" may project any amount)? If wall-mounted objects project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.2			Yes ☐ No ☐ N/A ■
3.8B	Protruding Objects	Do free-standing objects mounted on posts with leading edges between 27" and 80" high (such as a sign or telephone) overhang 12" or less above the ground or finish floor? If free-standing objects mounted on posts project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.3			Yes ☐ No ☐ N/A ■
3.9B	Cross Slope	Is the cross slope of the accessible route of travel no greater than 1:48? 11B-403.3			Yes ■ No ☐ N/A ☐
3.10B	Running Slope	Is the slope of the accessible route of travel no greater than 1:20, unless it complies with item 12 below? 11B-403.3			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room Item Name: ROUTE TO/FROM (PK1) TO/FROM ENTRY/EXIT WALKWAY	ID No.:	Floor No.:	Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.11B	Running Slope	Where the slope is greater than 1:20, does it comply with the requirements for ramps? (Use Form 7 - Ramps) 11B-402.2, 11B-405			Yes ☐ No ☐ N/A ■
3.12B	Changes in Level	When walkway levels change, is the vertical distance between them less than 1/4 inch? **OR** Are changes in level between 1/4 inch and 1/2 inch beveled with a slope no greater than 1:2? 11B-303.2, 11B-303.3	CHANGES IN LEVEL > 1/4" @ CONC APRON/ DRIVE AILE PAVERS		Yes ☐ No ■ N/A ☐
3.13B	Changes in Level	Are curb ramps, ramps, or elevators used for changes in level greater than 1/2 inch? (Lifts may only be used in certain limited situations) 11B-303.4			Yes ■ No ☐ N/A ☐
3.14B	Changes in Level	Are curb ramps, ramps, or elevators compliant? (Use Form 4 - Curb Ramps; Form 7 - Ramps; or Form 13 - Elevators) 11B-405, 11B-406, 11B-407	NO DETECTABLE WARNING - SEE SURVEY FORM		Yes ☐ No ■ N/A ☐
3.15B	Surface	Are accessible route surfaces stable, firm and slip-resistant? 11B-302.1	LOOSE ASPHALT @ SOUTH (PK1) ROUTE TO CURB RAMP		Yes ☐ No ■ N/A ☐
3.16B	Grates	Is the smaller dimension of a grate opening no more than 1/2 inch, and are long dimensions of rectangular gaps placed perpendicular to the usual direction of travel? 11B-302.3			Yes ☐ No ☐ N/A ■
3.17B	Abrupt Changes in Level >4"	Is the site free of abrupt changes in level adjacent to pedestrian areas exceeding 4" vertical except (1) between a walk or sidewalk and an adjacent street or driveway, or (2) where a 6" high warning curb or 42" high guard is provided to warn of a potential drop off? 11B-303.5			Yes ■ No ☐ N/A ☐
3.18B	Abrupt Changes in Level >30"	Is the site free of abrupt changes in level adjacent to pedestrian areas exceeding 30" vertical except were a 42" high guard is provided to prevent persons from falling off the open edge? See 1013.2 for exceptions.			Yes ☐ No ☐ N/A ■
3.19B	Entrance Signs	Are signs including the International Symbol of Accessibility at primary public entrances and at every major junction where the accessible route of travel diverges from the regular circulation path compliant? (Use Form 19 - Signage) 11B-216.6			Yes ■ No ☐ N/A ☐
3.20B	Directions to Accessible Entrance	When not all entrances are accessible, is there directional signage indicating the accessible route to an accessible entrance? 11B-216.6			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.21B	Hazardous Vehicular Areas - Detectable Warnings	If a walk crosses or adjoins the vehicular way and the walking surface is not separated by curbs, railings, or other elements between the pedestrian areas and vehicular areas, is the boundary between the areas defined by a continuous detectable warning at least 36" wide complying with 11B-705.1? (Use Form 21 - Hazards) 11B-705.1.2.5			Yes ☐ No ☐ N/A ■
3.22B	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

CURB RAMPS

Survey Form 4

Space/Room Item Name: CURB RAMP SERVING THE OPEN PARKING FRONT (PK1)

Item No.:

Floor No.:

Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
4.1	Curb Ramp Location	Is there a curb ramp wherever an accessible route crosses a curb? 11B-406.5.1			Yes ■ No ☐ N/A ☐
4.2	Slope	Is the slope of the curb ramp the least possible slope but in no case more than 1:12 and a cross slope of 1:48 maximum? 11B-406.2.1, 11B-406.3.1, 11B 406.5.7			Yes ■ No ☐ N/A ☐
4.3	Transition	Is the transition from the curb ramp to the road or gutter flush and free of abrupt changes? 11B-406.5.8			Yes ■ No ☐ N/A ☐
4.4	Counter Slope	Are the running slopes of the road, gutter or accessible route adjoining the ramp no greater than1:20? 11B-406.5.8			Yes ■ No ☐ N/A ☐
4.5	Width	Is the width of the curb ramp, not including the flared sides, at least 48"? 11B-406.5.2			Yes ■ No ☐ N/A ☐
4.6	Landings/Curb Ramps/Blended Transitions	Are landings, curb ramps, and blended transitions subject to wet conditions designed to prevent the accumulation of water? 11B-405.10, 11B-406.5.5			Yes ■ No ☐ N/A ☐
4.7	Side Flare Slope	Do the flared sides have a slope of 1:10 or less (measured along the curb)? 11B-406.2.2			Yes ☐ No ☐ N/A ■
4.8	Built-up Curb Ramps	Are built-up curb ramps located so that they do not project into vehicular traffic lanes or parking access aisles? 11B-406.5.1			Yes ☐ No ☐ N/A ■
4.9	Detectable Warning	Does the curb ramp have detectable warning? 11B-406.5.12, 11B-705.1	NO DETECTABLE WARNING PROVIDED		Yes ☐ No ■ N/A ☐
4.10	Detectable Warning	Does the detectable warning consist of raised truncated domes, which contrast visually with adjoining surfaces (light-on-dark or dark-on-light), and is the material used to provide contrast an integral part of the walking surface? 11B-705.1.1.3			Yes ☐ No ☐ N/A ■
4.11	Parked Vehicles	Are curb ramps located or protected so that they will not be obstructed by parked vehicles? 11B-406.5.1			Yes ■ No ☐ N/A ☐
4.12	Curb Ramps at Crosswalks	Where pedestrian crossings are identified by lines, are curb ramps wholly contained within the crosswalk lines, except for the flared sides? 11B-406.5.1			Yes ☐ No ☐ N/A ■
4.13	Top Landing at Curb Ramps or Blended Transition	Is there a landing at the top of curb ramps and blended transitions that is minimum 48" long? Is the width as wide as the curb ramp with a slope of 1:48 maximum? 11B-406.5.10			Yes ■ No ☐ N/A ☐
4.14	Straight Curb	If the diagonal curb ramp has flared sides, is there at least a 24" segment of straight curb located on each side of the curb ramp within the crosswalk lines? 11B-406.5.3			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

CURB RAMPS

Survey Form 4

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
CURB RAMP SERVING (PK1)			139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
4.15	Grooved Border	Do curb ramps have a grooved border 12" wide along the top of the curb ramp at the level surface of the top landing and at the outside edges of the flared sides? Are the grooves ¼" wide x ¼" deep, at ¾" o.c.? 11B-406.5.11	NOT REQUIRED PER 2013 CBC JULY 1, 2015 SUPPLEMENT		Yes ☐ No ■ N/A ☐
4.16	Island	Where the accessible route of travel crosses a median or island, is the island curb cut through at street level? **OR** Are there curb ramps on both sides and a level area at least 48" long and 60" wide between them? (With a 6" high curb, the island will be at least 16 feet wide.) Are there detectable warnings? 11B-406.6			Yes ☐ No ☐ N/A ■
4.17	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities



OPEN PARKING FRONT (PK1)

OPEN PARKING FRONT (PK1)

ROUTE TO/FROM (PK1) TO/FROM THE CURB RAMP SERVING THE ENTRY/EXIT WALKWAY

CURB RAMP SERVING THE OPEN PARKING FRONT (PK1)

PARKING

Survey Form 1

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
OPEN PARKING REAR (PK2)			139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
1.1	Off-site Parking Spaces	If no on-site parking is provided, is there accessible parking provided off-site nearby? (Note: Accessible parking for employees or visitors or both may be provided either in the public rights-of-way or in an off-site facility.) 11B-208.1, 11B-208.3.1			Yes ☐ No ☐ N/A ■
1.2	Number - Accessible Parking Spaces	Where parking spaces are provided for self-parking by employees or visitors or both, is the required number of accessible parking spaces provided? (See Minimum Requirements Summary Sheet A) (Note: All or some of the accessible parking spaces may be in a different location if equivalent or greater accessibility is ensured.) 11B-208.2, Table 11B-208.2	± 37 SPACES 2 ACCESSIBLE SPACES REQ. 1 PROVIDED		Yes ☐ No ■ N/A ☐
1.3	Each Area/Lot	Are the accessible parking spaces located in each specific area/lot? OR If the accessible parking spaces are in a different location, is equivalent or greater accessibility provided in terms of distance from the accessible entrance, user cost and convenience? 11B-208.2			Yes ■ No ☐ N/A ☐
1.4	Van Accessible Spaces	Is one in every six accessible parking spaces (but not less than one) designated "van accessible"? 11B-208.2.4, 11B-208.2			Yes ■ No ☐ N/A ☐
1.5	Location - Serving Accessible Entrance	Are accessible parking spaces which serve a particular building on the shortest accessible route of travel from adjacent parking to the building's accessible entrance? 11B-208.1, 11B-208.3			Yes ☐ No ■ N/A ☐
1.6	Lot Layout	Are parking stalls arranged so that persons with disabilities are not compelled to wheel or walk behind parked cars other than their own? 11B-502.7.1			Yes ■ No ☐ N/A ☐
1.7	Serving Multiple Accessible Entrances	If the building has multiple accessible entrances with adjacent parking, are the accessible parking spaces dispersed and on the shortest accessible route of travel to the parking facility's accessible pedestrian entrance? 11B-208.1, 11B-208.3.1			Yes ☐ No ■ N/A ☐
1.8	Separate Parking Facility	Where a parking facility does not serve a particular building, are the accessible parking spaces on the shortest accessible route of travel to the parking facility's accessible pedestrian entrance? 11B-208.1, 11B-208.3.1			Yes ☐ No ☐ N/A ■
1.9	Parking Space Width - Car	Are accessible car parking spaces, at least 9' wide and 18' long with a demarcated access aisle? (two spaces may share a common aisle)			Yes ■ No ☐ N/A ☐
1.10	Parking Space Width - Van	Are accessible van parking spaces at least 12' wide and 18' long with a demarcated access aisle?	ALT. 9' WIDE & 18' LONG		Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
1.11	Van Access Aisle	If the parking space is designated as "van accessible," is the adjacent access aisle at least 5' wide by 18' long and located on the passenger side of the vehicle space? See 1.12 below for van space and access aisle size exception. 11B-502.2 exception	ALT. 9' WIDE & 18' LONG		Yes ☐ No ☐ N/A ■
1.12	Car & Van Access Parking	If there is a 5' access aisle shared by a car and van, is the car parking space 9' wide and the van parking space 12' wide with 18' long minimum spaces or if the van parking space is 9' wide, is the access aisle 8' wide with 18' long minimum spaces? 11B-502.2			Yes ■ No ☐ N/A ☐
1.13	Car Access Aisles	Are all other access aisles at least 5' wide and 18' long, extending the full required length of the parking space they serve? 11B-502.3.1, 11B-502.3.2			Yes ☐ No ☐ N/A ■
1.14	Level Surface	Are the accessible parking spaces and access aisles level with no slope greater than 1:48 in all directions? (This means a curb ramp cannot project into the access aisle.) 11B-502.4	3.7%-3.8% CURB RAMP W/IN ACCESS AISLE		Yes ☐ No ■ N/A ☐
1.15	Surface	Are access aisles stable, firm, and slip resistant and clear of the vehicular way? 11B-302, 11B-502.3.4			Yes ■ No ☐ N/A ☐
1.16	Access Aisle and Accessible Route	Does each access aisle connect directly to an accessible route of travel, and on the shortest accessible route? (Use Form 3 - Exterior Routes of Travel) 11B-208.3.1			Yes ☐ No ■ N/A ☐
1.17	Parking Signs	Does each accessible parking space have a reflectorized sign visible from each stall showing the ISA? 11B-502.6			Yes ■ No ☐ N/A ☐
1.18	Car & Van Accessible Parking Signs	Do van accessible spaces have a sign stating "Van Accessible" below the ISA and do both car and van have additional language or an additional sign below the ISA stating "Minimum fine $250" and is it minimum 60" minimum AFF or ground? 11B-502.6, 11B-502.6.2	NO "NO PARKING" SIGN PROVIDED		Yes ☐ No ■ N/A ☐
1.19	Pavement Sign	Is there a minimum 36" square ISA painted on the pavement at the rear of the stall, centered a maximum of 6" from the centerline of the parking space and aligned with the end of the parking space length? 11B-502.6.4.1, 11B-502.6.4.2			Yes ■ No ☐ N/A ☐
1.20	Marking	Is the access aisle marked with a blue painted borderline around the perimeter and marked with hatched lines a maximum of 36' OC in a color contrasting with the aisle surface and are the words "NO PARKING" provided in each access aisle, painted in white, 12" high letters? 11B-502.3.3			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
1.21	Tow-away Sign	Is there a tow-away sign posted in a conspicuous place at each entrance to off–street parking lot, or immediately adjacent to and visible from each accessible stall? 11B-502.8	SIGN @ ONLY (1) OF (3) ENTRANCES & SIGN IS GOOD		Yes ☐ No ■ N/A ☐
1.22	Van Accessible Spaces - Vertical Clearance	Do accessible spaces and their access aisles have a vertical clearance of at least 98"? 11B-502.5			Yes ■ No ☐ N/A ☐
1.23	Van Accessible Spaces - Vertical Clearance	Does one vehicular access route to and from van accessible spaces have a vertical clearance of at least 98"? (Van accessible spaces may be grouped on one level of a parking structure.) 11B-502.5			Yes ■ No ☐ N/A ☐
1.24	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

CURB RAMPS

Survey Form 4

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
CURB RAMP SERVING (PK2)			139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check (Yes / No / N/A)
4.1	Curb Ramp Location	Is there a curb ramp wherever an accessible route crosses a curb? 11B-406.5.1			Yes ■ No □ N/A □
4.2	Slope	Is the slope of the curb ramp the least possible slope but in no case more than 1:12 and a cross slope of 1:48 maximum? 11B-406.2.1, 11B-406.3.1, 11B 406.5.7	11.5%		Yes □ No ■ N/A □
4.3	Transition	Is the transition from the curb ramp to the road or gutter flush and free of abrupt changes? 11B-406.5.8			Yes ■ No □ N/A □
4.4	Counter Slope	Are the running slopes of the road, gutter or accessible route adjoining the ramp no greater than1:20? 11B-406.5.8			Yes ■ No □ N/A □
4.5	Width	Is the width of the curb ramp, not including the flared sides, at least 48"? 11B-406.5.2			Yes ■ No □ N/A □
4.6	Landings/Curb Ramps/Blended Transitions	Are landings, curb ramps, and blended transitions subject to wet conditions designed to prevent the accumulation of water? 11B-405.10, 11B-406.5.5			Yes ■ No □ N/A □
4.7	Side Flare Slope	Do the flared sides have a slope of 1:10 or less (measured along the curb)? 11B-406.2.2	15.7% & 14.2%		Yes □ No ■ N/A □
4.8	Built-up Curb Ramps	Are built-up curb ramps located so that they do not project into vehicular traffic lanes or parking access aisles? 11B-406.5.1	PROJECTS INTO PARKING ACCESS AISLE		Yes □ No ■ N/A □
4.9	Detectable Warning	Does the curb ramp have detectable warning? 11B-406.5.12, 11B-705.1			Yes □ No ■ N/A □
4.10	Detectable Warning	Does the detectable warning consist of raised truncated domes, which contrast visually with adjoining surfaces (light-on-dark or dark-on-light), and is the material used to provide contrast an integral part of the walking surface? 11B-705.1.1.3			Yes □ No ■ N/A ■
4.11	Parked Vehicles	Are curb ramps located or protected so that they will not be obstructed by parked vehicles? 11B-406.5.1			Yes ■ No □ N/A □
4.12	Curb Ramps at Crosswalks	Where pedestrian crossings are identified by lines, are curb ramps wholly contained within the crosswalk lines, except for the flared sides? 11B-406.5.1			Yes □ No □ N/A ■
4.13	Top Landing at Curb Ramps or Blended Transition	Is there a landing at the top of curb ramps and blended transitions that is minimum 48" long? Is the width as wide as the curb ramp with a slope of 1:48 maximum? 11B-406.5.10			Yes ■ No □ N/A □
4.14	Straight Curb	If the diagonal curb ramp has flared sides, is there at least a 24" segment of straight curb located on each side of the curb ramp within the crosswalk lines? 11B-406.5.3			Yes □ No □ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
4.15	Grooved Border	Do curb ramps have a grooved border 12" wide along the top of the curb ramp at the level surface of the top landing and at the outside edges of the flared sides? Are the grooves ¼" wide x ¼" deep, at ¾" o.c.? 11B-406.5.11	NOT REQUIRED PER CBC JULY 1, 2015 SUPPLEMENT		Yes ☐ No ■ N/A ☐
4.16	Island	Where the accessible route of travel crosses a median or island, is the island curb cut through at street level? **OR** Are there curb ramps on both sides and a level area at least 48" long and 60" wide between them? (With a 6" high curb, the island will be at least 16 feet wide.) Are there detectable warnings? 11B-406.6			Yes ☐ No ☐ N/A ■
4.17	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities



OPEN PARKING REAR (PK2)



CURB RAMP SERVING THE OPEN PARKING REAR (PK2)

PARKING

Survey Form 1

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
COVERED PARKING (PK3)			139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
1.1	Off-site Parking Spaces	If no on-site parking is provided, is there accessible parking provided off-site nearby? (Note: Accessible parking for employees or visitors or both may be provided either in the public rights-of-way or in an off-site facility.) 11B-208.1, 11B-208.3.1			Yes ☐ No ☐ N/A ■
1.2	Number - Accessible Parking Spaces	Where parking spaces are provided for self-parking by employees or visitors or both, is the required number of accessible parking spaces provided? (See Minimum Requirements Summary Sheet A) (Note: All or some of the accessible parking spaces may be in a different location if equivalent or greater accessibility is ensured.) 11B-208.2, Table 11B-208.2	NO ACCESSIBLE PARKING SPACES PROVIDED W/IN THE COVERED PARKING AREA		Yes ☐ No ■ N/A ☐
1.3	Each Area/Lot	Are the accessible parking spaces located in each specific area/lot? OR If the accessible parking spaces are in a different location, is equivalent or greater accessibility provided in terms of distance from the accessible entrance, user cost and convenience? 11B-208.2			Yes ☐ No ■ N/A ☐
1.4	Van Accessible Spaces	Is one in every six accessible parking spaces (but not less than one) designated "van accessible"? 11B-208.2.4, 11B-208.2			Yes ☐ No ☐ N/A ■
1.5	Location - Serving Accessible Entrance	Are accessible parking spaces which serve a particular building on the shortest accessible route of travel from adjacent parking to the building's accessible entrance? 11B-208.1, 11B-208.3			Yes ☐ No ☐ N/A ■
1.6	Lot Layout	Are parking stalls arranged so that persons with disabilities are not compelled to wheel or walk behind parked cars other than their own? 11B-502.7.1			Yes ☐ No ☐ N/A ■
1.7	Serving Multiple Accessible Entrances	If the building has multiple accessible entrances with adjacent parking, are the accessible parking spaces dispersed and on the shortest accessible route of travel to the parking facility's accessible pedestrian entrance? 11B-208.1, 11B-208.3.1			Yes ☐ No ☐ N/A ■
1.8	Separate Parking Facility	Where a parking facility does not serve a particular building, are the accessible parking spaces on the shortest accessible route of travel to the parking facility's accessible pedestrian entrance? 11B-208.1, 11B-208.3.1			Yes ☐ No ☐ N/A ■
1.9	Parking Space Width - Car	Are accessible car parking spaces, at least 9' wide and 18' long with a demarcated access aisle? (two spaces may share a common aisle)			Yes ☐ No ☐ N/A ■
1.10	Parking Space Width - Van	Are accessible van parking spaces at least 12' wide and 18' long with a demarcated access aisle?			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
1.11	Van Access Aisle	If the parking space is designated as "van accessible," is the adjacent access aisle at least 5' wide by 18' long and located on the passenger side of the vehicle space? See 1.12 below for van space and access aisle size exception. 11B-502.2 exception			Yes ☐ No ☐ N/A ■
1.12	Car & Van Access Parking	If there is a 5' access aisle shared by a car and van, is the car parking space 9' wide and the van parking space 12' wide with 18' long minimum spaces or if the van parking space is 9' wide, is the access aisle 8' wide with 18' long minimum spaces? 11B-502.2			Yes ☐ No ☐ N/A ■
1.13	Car Access Aisles	Are all other access aisles at least 5' wide and 18' long, extending the full required length of the parking space they serve? 11B-502.3.1, 11B-502.3.2			Yes ☐ No ☐ N/A ■
1.14	Level Surface	Are the accessible parking spaces and access aisles level with no slope greater than 1:48 in all directions? (This means a curb ramp cannot project into the access aisle.) 11B-502.4			Yes ☐ No ☐ N/A ■
1.15	Surface	Are access aisles stable, firm, and slip resistant and clear of the vehicular way? 11B-302, 11B-502.3.4			Yes ☐ No ☐ N/A ■
1.16	Access Aisle and Accessible Route	Does each access aisle connect directly to an accessible route of travel, and on the shortest accessible route? (Use Form 3 - Exterior Routes of Travel) 11B-208.3.1			Yes ☐ No ☐ N/A ■
1.17	Parking Signs	Does each accessible parking space have a reflectorized sign visible from each stall showing the ISA? 11B-502.6			Yes ☐ No ☐ N/A ■
1.18	Car & Van Accessible Parking Signs	Do van accessible spaces have a sign stating "Van Accessible" below the ISA and do both car and van have additional language or an additional sign below the ISA stating "Minimum fine $250" and is it minimum 60" minimum AFF or ground? 11B-502.6, 11B-502.6.2			Yes ☐ No ☐ N/A ■
1.19	Pavement Sign	Is there a minimum 36" square ISA painted on the pavement at the rear of the stall, centered a maximum of 6" from the centerline of the parking space and aligned with the end of the parking space length? 11B-502.6.4.1, 11B-502.6.4.2			Yes ☐ No ☐ N/A ■
1.20	Marking	Is the access aisle marked with a blue painted borderline around the perimeter and marked with hatched lines a maximum of 36' OC in a color contrasting with the aisle surface and are the words "NO PARKING" provided in each access aisle, painted in white, 12" high letters? 11B-502.3.3			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
1.21	Tow-away Sign	Is there a tow-away sign posted in a conspicuous place at each entrance to off–street parking lot, or immediately adjacent to and visible from each accessible stall? 11B-502.8			Yes ☐ No ■ N/A ☐
1.22	Van Accessible Spaces - Vertical Clearance	Do accessible spaces and their access aisles have a vertical clearance of at least 98"? 11B-502.5	THE COVERED PARKING AREA CLEARANCE IS >98"		Yes ☐ No ☐ N/A ■
1.23	Van Accessible Spaces - Vertical Clearance	Does one vehicular access route to and from van accessible spaces have a vertical clearance of at least 98"? (Van accessible spaces may be grouped on one level of a parking structure.) 11B-502.5			Yes ☐ No ☐ N/A ■
1.24	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

- ✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

COVERED PARKING (PK3)

Facility
Name: DEPARTMENT OF REHABILITATION

RESD
Project No.: 139602

Exterior Routes

An accessible route must connect the following elements. Accessible routes must, to the maximum extent feasible, coincide with the routes for the general public. If accessible routes do not exist between these elements, that is a violation. If accessible routes do exist then the completed survey will reveal their satisfactory and unsatisfactory features. For interior accessible routes , see Summary Sheet D.1.

Use Survey Form 3A for accessible routes in the public right-of-way, if adjacent to the property line of the site. Use Survey Form 3B for accessible routes within the property line. Note that the landlord typically must notify the entity that has authority over the public right-of-way and request in writing modification of any identified barriers.

At least one exterior accessible route of complying with CBC 11B-206.2.1 must be provided within the site from accessible parking spaces and accessible passenger loading zones; public streets and sidewalks; and public transportation stops to the accessible building or facility entrance they serve.

List all routes which must be accessible in the following table and survey each of these areas with a separate copy of SF3A or SF3B - Exterior Routes. If you encounter walkways, ramps, curb ramps, stairs, lifts, or elevators, survey that element with its specific survey form:

ID	Name/location of routes of travel (or key number on site plan)		
	Between:	**And:**	**3A or 3B**
ER1	KAWEAH COURT CITY SIDEWALK ADJACENT TO THE PROPERTY LINE		3A
ER2	KAWEAH COURT CITY SIDEWALK	ON-SITE ENTRY WALKWAYS	3B
ER3	REAR ACCESSIBLE PARKING (PK2)	MAIN (WEST) BUILDING ENTRANCE	3B
ER4	REAR ACCESSIBLE PARKING (PK2)	REAR (EAST) BUILDING ENTRANCE	3B
ER5	MAIN (WEST) ENTRANCE WALKWAY	EXTERIOR WEST PATIO AREA	3B
ER6			
ER7			

*Indicate the number of Survey Forms attached to Summary Sheet C in the **No**. field.*

Form	Item	No.		Form	Item	No.		Form	Item	No.
SF3	Exterior Routes (A+B)	5		SF4	Curb Ramps	1		SF5	Drinking Fountains	
SF6	Telephones			SF7	Ramps			SF8	Stairs	
SF9	Platform Lifts			SF13	Elevators			SF19	Signage	
SF21	Hazards			SF ..				SF		

EXTERIOR ROUTES OF TRAVEL (Public Rights-of-Way Only)

Survey Form 3A

Space/Room Item Name:	ID No.:	Floor No.:	Project No.:
KAWEAH COURT CITY SIDEWALK ADJACENT TO THE PROPERTY LINE	ER1		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions Or Survey Comments	Lessor/Architect Comments	Check
3.1A	Accessible Route of Travel in the Public Right of Way	Is there an accessible route of travel linking an accessible site entrance with the following, if provided and if adjacent to the property line of the site: public transportation stops, passenger loading zones, accessible parking, and public sidewalks? If more than one route is provided, are all routes accessible? 11B-206.2.1, 11B-402			Yes ☐ No ■ N/A ☐
3.2A	Width	Is the accessible route of travel at least 48" wide except at doorways or gates? The clear width can be reduced to 32" minimum for a length of 24" maximum provided that reduced width segments are separated by segments that are 48" long minimum and 36" wide minimum? 11B-302.1, 11B-403.5.1, Exception 1, 3	NOT @ THE CONTRAC DROP BOX LOCATED W/IN THE KAWEAH CART CITY SIDEWALK		Yes ☐ No ■ N/A ☐
3.3A	Surface	Are accessible route surfaces stable, firm and slip-resistant? 11B-302.1			Yes ■ No ☐ N/A ☐
3.4A	Head Room	Is there at least 80" clear head room within the pedestrian circulation area, including the accessible route of travel? If the vertical clearance is less than 80" high, is a guardrail or other barrier provided? 11B-307.4			Yes ■ No ☐ N/A ☐
3.5A	Protruding Objects	If wall-mounted objects have leading edges between 27" and 80" from the floor, do they project less than 4" into the circulation path (objects with leading edges at or below 27" may project any amount)? If wall-mounted objects project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.2			Yes ☐ No ☐ N/A ■
3.6A	Protruding Objects	Do free-standing objects mounted on posts with leading edges between 27" and 80" high (such as a sign or telephone) overhang 12" or less above the ground or finish floor? If free-standing objects mounted on posts project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.3			Yes ☐ No ☐ N/A ■
3.7A	Cross Slope	Is the cross slope of the accessible route of travel no greater than 1:48? 11B-403.3	NOT THROUGH THE KAWEAH CT. DRIVE APPROACHES		Yes ☐ No ■ N/A ☐
3.8A	Running Slope	Is the slope of the accessible route of travel no greater than 1:20 (5 percent), unless it complies with the requirements of a ramp or it does not exceed the grade of the adjacent roadway? 11B-403.3	NOT @ THE KAWEAH CT. DRIVE APPROACHES		Yes ☐ No ■ N/A ☐
3.9A	Changes in Level	When walkway levels change abruptly, is the vertical distance between them less than 1/4 inch? **OR** Are changes in level between 1/4 inch and 1/2 inch beveled with a slope no greater than 1:2? 11B-303.2, 11B-303.3			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

EXTERIOR ROUTES OF TRAVEL (Public Rights-of-Way Only)

Survey Form 3A

Space/Room Item Name: KAWEAH COURT CITY SIDWALK ADJACENT TO THE PROPERTY LINE	ID No.: ER1	Floor No.:	Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions Or Survey Comments	Lessor/Architect Comments	Check
3.10A	Changes in Level	Are all curb ramps and ramps compliant? (See Form 4 - Curb Ramps or Form 7 - Ramps) 11B-405, 11B-406			Yes ☐ No ☐ N/A ■
3.11A	Grates and Drains	Is the smaller dimension of a grate opening in the accessible route of travel no more than 1/2 inch, and are long dimensions of rectangular gaps placed perpendicular to the usual direction of travel? 11B-302.3			Yes ☐ No ☐ N/A ■
3.12A	Hazardous Vehicular Areas - Detectable Warnings	If an accessible route of travel crosses or adjoins the vehicular way and the walking surface is not separated by curbs, railings, or other elements between the pedestrian areas and vehicular areas, is the boundary between the areas defined by a continuous detectable warning at least 36" wide complying with 11B-705.1? 11B-705.1.2.5			Yes ☐ No ☐ N/A ■
3.13A	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

KAWEAH COURT CITY SIDEWALK ADJACENT TO THE PROPERTY LINE (ER1)

KAWEAH COURT CITY SIDEWALK ADJACENT TO THE PROPERTY LINE (ER1)

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room Item Name: KAWEAH COURT CITY SIDEWALK TO ON-SITE ENTRY WALKWAYS	ID No.: ER2	Floor No.:	Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.1B	On-site Accessible Route of Travel	Is there an accessible route of travel within the property line of the site linking an accessible building entrance with site arrival points serving the following, if provided: public transportation stops, passenger loading zones, accessible parking, and public sidewalks? 11B-206.2.1, 11B-402	NO ACCESSIBLE ROUTE SERVING THE PUBLIC SIDEWALK		Yes ☐ No ■ N/A ☐
3.2B	Route for General Public	Does the accessible route of travel, to the maximum extent feasible, coincide with the route for the general public? 11B-206, 11B-402	NO ROUTE SERVING THE CITY SIDEWALK		Yes ☐ No ☐ N/A ■
3.3B	Facilities Connected	Are there accessible routes of travel connecting all accessible buildings, facilities, elements and spaces on the same site with one another? 11B-206.2.2, 11B-402			Yes ☐ No ■ N/A ☐
3.4B	Width	Is the accessible route of travel at least 48" wide? The clear width can be reduced to 32" minimum for a length of 24" maximum provided that reduced width segments are separated by segments that are 48" long minimum and 36" wide minimum? 11B-302.1, 11B-403.5.1, Exception1, 3			Yes ☐ No ☐ N/A ■
3.5B	Passing Spaces	If the accessible route of travel is less than 60" wide, are there passing spaces at least 60" by 60" or intersecting walks provided, allowing passing at reasonable intervals not exceeding 200'? 11B-403.5.3			Yes ☐ No ☐ N/A ■
3.6B	Head Room	Is there at least 80" clear head room within the pedestrian circulation area, including the accessible route of travel? If the vertical clearance is less than 80" high, is a guardrail or other barrier provided? 11B-307.4			Yes ☐ No ☐ N/A ■
3.7B	Protruding Objects	If wall-mounted objects have leading edges between 27" and 80" from the floor, do they project less than 4" into the circulation path (objects with leading edges at or below 27" may project any amount)? If wall-mounted objects project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.2			Yes ☐ No ☐ N/A ■
3.8B	Protruding Objects	Do free-standing objects mounted on posts with leading edges between 27" and 80" high (such as a sign or telephone) overhang 12" or less above the ground or finish floor? If free-standing objects mounted on posts project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.3			Yes ☐ No ☐ N/A ■
3.9B	Cross Slope	Is the cross slope of the accessible route of travel no greater than 1:48? 11B-403.3			Yes ☐ No ☐ N/A ■
3.10B	Running Slope	Is the slope of the accessible route of travel no greater than 1:20, unless it complies with item 12 below? 11B-403.3			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room Item Name:	ID No.:	Floor No.:	Project No.:
KAWEAH COURT CITY SIDEWALK TO ON-SITE ENTRY WALKWAYS	ER2		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.11B	Running Slope	Where the slope is greater than 1:20, does it comply with the requirements for ramps? (Use Form 7 - Ramps) 11B-402.2, 11B-405			Yes ☐ No ☐ N/A ■
3.12B	Changes in Level	When walkway levels change, is the vertical distance between them less than 1/4 inch? **OR** Are changes in level between 1/4 inch and 1/2 inch beveled with a slope no greater than 1:2? 11B-303.2, 11B-303.3			Yes ☐ No ☐ N/A ■
3.13B	Changes in Level	Are curb ramps, ramps, or elevators used for changes in level greater than 1/2 inch? (Lifts may only be used in certain limited situations) 11B-303.4			Yes ☐ No ☐ N/A ■
3.14B	Changes in Level	Are curb ramps, ramps, or elevators compliant? (Use Form 4 - Curb Ramps; Form 7 - Ramps; or Form 13 - Elevators) 11B-405, 11B-406, 11B-407			Yes ☐ No ☐ N/A ■
3.15B	Surface	Are accessible route surfaces stable, firm and slip-resistant? 11B-302.1			Yes ☐ No ☐ N/A ■
3.16B	Grates	Is the smaller dimension of a grate opening no more than 1/2 inch, and are long dimensions of rectangular gaps placed perpendicular to the usual direction of travel? 11B-302.3			Yes ☐ No ☐ N/A ■
3.17B	Abrupt Changes in Level >4"	Is the site free of abrupt changes in level adjacent to pedestrian areas exceeding 4" vertical except (1) between a walk or sidewalk and an adjacent street or driveway, or (2) where a 6" high warning curb or 42" high guard is provided to warn of a potential drop off? 11B-303.5			Yes ☐ No ☐ N/A ■
3.18B	Abrupt Changes in Level >30"	Is the site free of abrupt changes in level adjacent to pedestrian areas exceeding 30" vertical except were a 42" high guard is provided to prevent persons from falling off the open edge? See 1013.2 for exceptions.			Yes ☐ No ☐ N/A ■
3.19B	Entrance Signs	Are signs including the International Symbol of Accessibility at primary public entrances and at every major junction where the accessible route of travel diverges from the regular circulation path compliant? (Use Form 19 - Signage) 11B-216.6			Yes ☐ No ☐ N/A ■
3.20B	Directions to Accessible Entrance	When not all entrances are accessible, is there directional signage indicating the accessible route to an accessible entrance? 11B-216.6			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room Item Name: KAWEAH COURT CITY SIDEWALK TO ON-SITE ENTRY WALKWAY	ID No.: ER2	Floor No.:	Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.21B	Hazardous Vehicular Areas - Detectable Warnings	If a walk crosses or adjoins the vehicular way and the walking surface is not separated by curbs, railings, or other elements between the pedestrian areas and vehicular areas, is the boundary between the areas defined by a continuous detectable warning at least 36" wide complying with 11B-705.1? (Use Form 21 - Hazards) 11B-705.1.2.5			Yes ☐ No ☐ N/A ■
3.22B	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

ROUTE OF TRAVEL BETWEEN THE KAWEAH COURT CITY SIDEWALK & ON-SITE ENTRY WALKWAYS (ER2)

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room Item Name: REAR ACCESSIBLE PARKING (PK2) TO MAIN(WEST) BUILDING ENTRY | ID No.: ER3 | Floor No.: | Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.1B	On-site Accessible Route of Travel	Is there an accessible route of travel within the property line of the site linking an accessible building entrance with site arrival points serving the following, if provided: public transportation stops, passenger loading zones, accessible parking, and public sidewalks? 11B-206.2.1, 11B-402			Yes ☐ No ■ N/A ☐
3.2B	Route for General Public	Does the accessible route of travel, to the maximum extent feasible, coincide with the route for the general public? 11B-206, 11B-402			Yes ☐ No ■ N/A ☐
3.3B	Facilities Connected	Are there accessible routes of travel connecting all accessible buildings, facilities, elements and spaces on the same site with one another? 11B-206.2.2, 11B-402			Yes ☐ No ■ N/A ☐
3.4B	Width	Is the accessible route of travel at least 48" wide? The clear width can be reduced to 32" minimum for a length of 24" maximum provided that reduced width segments are separated by segments that are 48" long minimum and 36" wide minimum? 11B-302.1, 11B-403.5.1, Exception1, 3	NOT IN FRONT OF PARKED VEHICLES OVERHANGING THE WALKWAYS		Yes ☐ No ■ N/A ☐
3.5B	Passing Spaces	If the accessible route of travel is less than 60" wide, are there passing spaces at least 60" by 60" or intersecting walks provided, allowing passing at reasonable intervals not exceeding 200'? 11B-403.5.3			Yes ☐ No ☐ N/A ■
3.6B	Head Room	Is there at least 80" clear head room within the pedestrian circulation area, including the accessible route of travel? If the vertical clearance is less than 80" high, is a guardrail or other barrier provided? 11B-307.4			Yes ■ No ☐ N/A ☐
3.7B	Protruding Objects	If wall-mounted objects have leading edges between 27" and 80" from the floor, do they project less than 4" into the circulation path (objects with leading edges at or below 27" may project any amount)? If wall-mounted objects project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.2			Yes ☐ No ☐ N/A ■
3.8B	Protruding Objects	Do free-standing objects mounted on posts with leading edges between 27" and 80" high (such as a sign or telephone) overhang 12" or less above the ground or finish floor? If free-standing objects mounted on posts project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.3			Yes ☐ No ☐ N/A ■
3.9B	Cross Slope	Is the cross slope of the accessible route of travel no greater than 1:48? 11B-403.3	2.6%-3.3% SEE PHOTOS		Yes ☐ No ■ N/A ☐
3.10B	Running Slope	Is the slope of the accessible route of travel no greater than 1:20, unless it complies with item 12 below? 11B-403.3			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room Item Name: REAR ACCESSIBLE PARKING (PK2) TO MAIN (WEST) BUILDING ENTRY

ID No.: ER3

Floor No.:

Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.11B	Running Slope	Where the slope is greater than 1:20, does it comply with the requirements for ramps? (Use Form 7 - Ramps) 11B-402.2, 11B-405			Yes ☐ No ☐ N/A ■
3.12B	Changes in Level	When walkway levels change, is the vertical distance between them less than 1/4 inch? **OR** Are changes in level between 1/4 inch and 1/2 inch beveled with a slope no greater than 1:2? 11B-303.2, 11B-303.3			Yes ☐ No ■ N/A ☐
3.13B	Changes in Level	Are curb ramps, ramps, or elevators used for changes in level greater than 1/2 inch? (Lifts may only be used in certain limited situations) 11B-303.4			Yes ■ No ☐ N/A ☐
3.14B	Changes in Level	Are curb ramps, ramps, or elevators compliant? (Use Form 4 - Curb Ramps; Form 7 - Ramps; or Form 13 - Elevators) 11B-405, 11B-406, 11B-407	NO TRUNCATED DOME DETECTABLE WARNING		Yes ☐ No ■ N/A ☐
3.15B	Surface	Are accessible route surfaces stable, firm and slip-resistant? 11B-302.1			Yes ■ No ☐ N/A ☐
3.16B	Grates	Is the smaller dimension of a grate opening no more than 1/2 inch, and are long dimensions of rectangular gaps placed perpendicular to the usual direction of travel? 11B-302.3			Yes ☐ No ☐ N/A ■
3.17B	Abrupt Changes in Level >4"	Is the site free of abrupt changes in level adjacent to pedestrian areas exceeding 4" vertical except (1) between a walk or sidewalk and an adjacent street or driveway, or (2) where a 6" high warning curb or 42" high guard is provided to warn of a potential drop off? 11B-303.5			Yes ■ No ☐ N/A ☐
3.18B	Abrupt Changes in Level >30"	Is the site free of abrupt changes in level adjacent to pedestrian areas exceeding 30" vertical except were a 42" high guard is provided to prevent persons from falling off the open edge? See 1013.2 for exceptions.			Yes ☐ No ☐ N/A ■
3.19B	Entrance Signs	Are signs including the International Symbol of Accessibility at primary public entrances and at every major junction where the accessible route of travel diverges from the regular circulation path compliant? (Use Form 19 - Signage) 11B-216.6			Yes ☐ No ■ N/A ☐
3.20B	Directions to Accessible Entrance	When not all entrances are accessible, is there directional signage indicating the accessible route to an accessible entrance? 11B-216.6			Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Space/Room Item Name: REAR ACCESSIBLE PARKING (PK2) TO MAIN (WEST) BUILDING ENTRY | ID No.: ER3 | Floor No.: | Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.21B	Hazardous Vehicular Areas - Detectable Warnings	If a walk crosses or adjoins the vehicular way and the walking surface is not separated by curbs, railings, or other elements between the pedestrian areas and vehicular areas, is the boundary between the areas defined by a continuous detectable warning at least 36" wide complying with 11B-705.1? (Use Form 21 - Hazards) 11B-705.1.2.5			Yes ☐ No ☐ N/A ■
3.22B	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

- PARKED VEHICLES ARE ALLOTTED ±36" OF OVERHANG OF WALKWAYS - IT REQUIRES A MINIMUM 7' WIDE WALKWAY TO MAINTAIN MINIMUM 48" WIDE WALKWAYS/ ACCESSIBLE ROUTES OF TRAVEL - WHEEL STOPS MAY BE USED TO LIMIT THE OVERHANG DEPTH OF PARKED VEHICLES.

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities







(ER3) ROUTE OF TRAVEL BETWEEN THE REAR ACCESSIBLE PARKING (PK2) & THE MAIN (WEST) BUILDING ENTRANCE

(ER3) ROUTE OF TRAVEL BETWEEN THE REAR ACCESSIBLE PARKING (PK2) & THE MAIN (WEST) BUILDING ENTRANCE

CURB RAMPS

Survey Form 4

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
NORTH CURB RAMP			139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
4.1	Curb Ramp Location	Is there a curb ramp wherever an accessible route crosses a curb? 11B-406.5.1			Yes ■ No ☐ N/A ☐
4.2	Slope	Is the slope of the curb ramp the least possible slope but in no case more than 1:12 and a cross slope of 1:48 maximum? 11B-406.2.1, 11B-406.3.1, 11B 406.5.7			Yes ■ No ☐ N/A ☐
4.3	Transition	Is the transition from the curb ramp to the road or gutter flush and free of abrupt changes? 11B-406.5.8			Yes ■ No ☐ N/A ☐
4.4	Counter Slope	Are the running slopes of the road, gutter or accessible route adjoining the ramp no greater than1:20? 11B-406.5.8			Yes ■ No ☐ N/A ☐
4.5	Width	Is the width of the curb ramp, not including the flared sides, at least 48"? 11B-406.5.2			Yes ■ No ☐ N/A ☐
4.6	Landings/Curb Ramps/Blended Transitions	Are landings, curb ramps, and blended transitions subject to wet conditions designed to prevent the accumulation of water? 11B-405.10, 11B-406.5.5			Yes ■ No ☐ N/A ☐
4.7	Side Flare Slope	Do the flared sides have a slope of 1:10 or less (measured along the curb)? 11B-406.2.2			Yes ☐ No ☐ N/A ■
4.8	Built-up Curb Ramps	Are built-up curb ramps located so that they do not project into vehicular traffic lanes or parking access aisles? 11B-406.5.1			Yes ☐ No ☐ N/A ■
4.9	Detectable Warning	Does the curb ramp have detectable warning? 11B-406.5.12, 11B-705.1			Yes ☐ No ■ N/A ☐
4.10	Detectable Warning	Does the detectable warning consist of raised truncated domes, which contrast visually with adjoining surfaces (light-on-dark or dark-on-light), and is the material used to provide contrast an integral part of the walking surface? 11B-705.1.1.3			Yes ☐ No ☐ N/A ■
4.11	Parked Vehicles	Are curb ramps located or protected so that they will not be obstructed by parked vehicles? 11B-406.5.1			Yes ■ No ☐ N/A ☐
4.12	Curb Ramps at Crosswalks	Where pedestrian crossings are identified by lines, are curb ramps wholly contained within the crosswalk lines, except for the flared sides? 11B-406.5.1			Yes ☐ No ☐ N/A ■
4.13	Top Landing at Curb Ramps or Blended Transition	Is there a landing at the top of curb ramps and blended transitions that is minimum 48" long? Is the width as wide as the curb ramp with a slope of 1:48 maximum? 11B-406.5.10			Yes ■ No ☐ N/A ☐
4.14	Straight Curb	If the diagonal curb ramp has flared sides, is there at least a 24" segment of straight curb located on each side of the curb ramp within the crosswalk lines? 11B-406.5.3			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
4.15	Grooved Border	Do curb ramps have a grooved border 12" wide along the top of the curb ramp at the level surface of the top landing and at the outside edges of the flared sides? Are the grooves ¼" wide x ¼" deep, at ¾" o.c.? 11B-406.5.11			Yes ☐ No ■ N/A ☐
4.16	Island	Where the accessible route of travel crosses a median or island, is the island curb cut through at street level? **OR** Are there curb ramps on both sides and a level area at least 48" long and 60" wide between them? (With a 6" high curb, the island will be at least 16 feet wide.) Are there detectable warnings? 11B-406.6			Yes ☐ No ☐ N/A ■
4.17	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ■ N/A ☐

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

- THE ASPHALT DRIVE AISLE AT THE LOWER TRANSITION OF THE CURB RAMP IS LOOSE & UNEVEN.

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

NORTH CURB RAMP

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room Item Name: REAR ACCESSIBLE PARKING (PKZ) TO REAR (EAST) BUILDING ENTRY

ID No.: ER4

Floor No.:

Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.1B	On-site Accessible Route of Travel	Is there an accessible route of travel within the property line of the site linking an accessible building entrance with site arrival points serving the following, if provided: public transportation stops, passenger loading zones, accessible parking, and public sidewalks? 11B-206.2.1, 11B-402			Yes ☐ No ■ N/A ☐
3.2B	Route for General Public	Does the accessible route of travel, to the maximum extent feasible, coincide with the route for the general public? 11B-206, 11B-402	REAR ACCESSIBLE PARKING IS NOT NEAR THE REAR BUILDING ENTRY		Yes ☐ No ■ N/A ☐
3.3B	Facilities Connected	Are there accessible routes of travel connecting all accessible buildings, facilities, elements and spaces on the same site with one another? 11B-206.2.2, 11B-402	MAIL BOXES GROUND SLOPES EXCEED 2%		Yes ☐ No ■ N/A ☐
3.4B	Width	Is the accessible route of travel at least 48" wide? The clear width can be reduced to 32" minimum for a length of 24" maximum provided that reduced width segments are separated by segments that are 48" long minimum and 36" wide minimum? 11B-302.1, 11B-403.5.1, Exception1, 3	NOT IN FRONT OF PARKED VEHICLES OVERHANGING THE WALKWAYS		Yes ☐ No ■ N/A ☐
3.5B	Passing Spaces	If the accessible route of travel is less than 60" wide, are there passing spaces at least 60" by 60" or intersecting walks provided, allowing passing at reasonable intervals not exceeding 200'? 11B-403.5.3			Yes ☐ No ☐ N/A ■
3.6B	Head Room	Is there at least 80" clear head room within the pedestrian circulation area, including the accessible route of travel? If the vertical clearance is less than 80" high, is a guardrail or other barrier provided? 11B-307.4			Yes ■ No ☐ N/A ☐
3.7B	Protruding Objects	If wall-mounted objects have leading edges between 27" and 80" from the floor, do they project less than 4" into the circulation path (objects with leading edges at or below 27" may project any amount)? If wall-mounted objects project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.2			Yes ☐ No ☐ N/A ■
3.8B	Protruding Objects	Do free-standing objects mounted on posts with leading edges between 27" and 80" high (such as a sign or telephone) overhang 12" or less above the ground or finish floor? If free-standing objects mounted on posts project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.3			Yes ☐ No ☐ N/A ■
3.9B	Cross Slope	Is the cross slope of the accessible route of travel no greater than 1:48? 11B-403.3	2.9% - 5.5%		Yes ☐ No ■ N/A ☐
3.10B	Running Slope	Is the slope of the accessible route of travel no greater than 1:20, unless it complies with item 12 below? 11B-403.3	NOT AT WALK TO REAR ENTRANCE		Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room Item Name: REAR ACCESSIBLE PARKING (PKG) TO REAR (EAST) BUILDING ENTRY

ID No.: ER4

Floor No.:

Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.11B	Running Slope	Where the slope is greater than 1:20, does it comply with the requirements for ramps? (Use Form 7 - Ramps) 11B-402.2, 11B-405			Yes ☐ No ■ N/A ☐
3.12B	Changes in Level	When walkway levels change, is the vertical distance between them less than 1/4 inch? **OR** Are changes in level between 1/4 inch and 1/2 inch beveled with a slope no greater than 1:2? 11B-303.2, 11B-303.3			Yes ☐ No ☐ N/A ■
3.13B	Changes in Level	Are curb ramps, ramps, or elevators used for changes in level greater than 1/2 inch? (Lifts may only be used in certain limited situations) 11B-303.4			Yes ☐ No ☐ N/A ■
3.14B	Changes in Level	Are curb ramps, ramps, or elevators compliant? (Use Form 4 - Curb Ramps; Form 7 - Ramps; or Form 13 - Elevators) 11B-405, 11B-406, 11B-407			Yes ☐ No ☐ N/A ■
3.15B	Surface	Are accessible route surfaces stable, firm and slip-resistant? 11B-302.1			Yes ■ No ☐ N/A ☐
3.16B	Grates	Is the smaller dimension of a grate opening no more than 1/2 inch, and are long dimensions of rectangular gaps placed perpendicular to the usual direction of travel? 11B-302.3			Yes ☐ No ☐ N/A ■
3.17B	Abrupt Changes in Level >4"	Is the site free of abrupt changes in level adjacent to pedestrian areas exceeding 4" vertical except (1) between a walk or sidewalk and an adjacent street or driveway, or (2) where a 6" high warning curb or 42" high guard is provided to warn of a potential drop off? 11B-303.5			Yes ■ No ☐ N/A ☐
3.18B	Abrupt Changes in Level >30"	Is the site free of abrupt changes in level adjacent to pedestrian areas exceeding 30" vertical except were a 42" high guard is provided to prevent persons from falling off the open edge? See 1013.2 for exceptions.			Yes ☐ No ☐ N/A ■
3.19B	Entrance Signs	Are signs including the International Symbol of Accessibility at primary public entrances and at every major junction where the accessible route of travel diverges from the regular circulation path compliant? (Use Form 19 - Signage) 11B-216.6			Yes ☐ No ■ N/A ☐
3.20B	Directions to Accessible Entrance	When not all entrances are accessible, is there directional signage indicating the accessible route to an accessible entrance? 11B-216.6			Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room / Item Name	ID No.:	Floor No.:	Project No.:
REAR ACCESSIBLE PARKING (PK2) / TO REAR (EAST) BUILDING ENTRY	ERA		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.21B	Hazardous Vehicular Areas - Detectable Warnings	If a walk crosses or adjoins the vehicular way and the walking surface is not separated by curbs, railings, or other elements between the pedestrian areas and vehicular areas, is the boundary between the areas defined by a continuous detectable warning at least 36" wide complying with 11B-705.1? (Use Form 21 - Hazards) 11B-705.1.2.5			Yes ☐ No ☐ N/A ■
3.22B	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ■ N/A ☐

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

- CLEAR GROUND SPACES ADJACENT TO THE EXTERIOR MAIL BOXES HAVE SLOPES THAT EXCEED 2%.

- PARKED VEHICLES ARE ALLOTTED ±36" OF OVERHANG OF WALKWAYS - IT REQUIRES A MINIMUM 7' WIDE WALKWAY TO MAINTAIN MINIMUM 48" WIDE WALKWAYS/ ACCESSIBLE ROUTES OF TRAVEL - WHEEL STOPS MAY BE USED TO LIMIT THE OVERHANG DEPTH OF PARKED VEHICLES.

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities









(ER4) ROUTE OF TRAVEL BETWEEN THE REAR ACCESSIBLE PARKING (PK2) & THE REAR (EAST) BUILDING ENTRANCE





(ER4) ROUTE OF TRAVEL BETWEEN THE REAR ACCESSIBLE PARKING (PK2) & THE REAR (EAST) BUILDING ENTRANCE

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room MAIN (WEST) ENTRANCE
Item Name: WALKWAY TO EXTERIOR PATIO AREA

ID No.: ER5

Floor No.:

Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.1B	On-site Accessible Route of Travel	Is there an accessible route of travel within the property line of the site linking an accessible building entrance with site arrival points serving the following, if provided: public transportation stops, passenger loading zones, accessible parking, and public sidewalks? 11B-206.2.1, 11B-402			Yes ☐ No ■ N/A ☐
3.2B	Route for General Public	Does the accessible route of travel, to the maximum extent feasible, coincide with the route for the general public? 11B-206, 11B-402			Yes ☐ No ☐ N/A ■
3.3B	Facilities Connected	Are there accessible routes of travel connecting all accessible buildings, facilities, elements and spaces on the same site with one another? 11B-206.2.2, 11B-402			Yes ☐ No ■ N/A ☐
3.4B	Width	Is the accessible route of travel at least 48" wide? The clear width can be reduced to 32" minimum for a length of 24" maximum provided that reduced width segments are separated by segments that are 48" long minimum and 36" wide minimum? 11B-302.1, 11B-403.5.1, Exception1, 3			Yes ■ No ☐ N/A ☐
3.5B	Passing Spaces	If the accessible route of travel is less than 60" wide, are there passing spaces at least 60" by 60" or intersecting walks provided, allowing passing at reasonable intervals not exceeding 200'? 11B-403.5.3			Yes ☐ No ☐ N/A ■
3.6B	Head Room	Is there at least 80" clear head room within the pedestrian circulation area, including the accessible route of travel? If the vertical clearance is less than 80" high, is a guardrail or other barrier provided? 11B-307.4			Yes ■ No ☐ N/A ☐
3.7B	Protruding Objects	If wall-mounted objects have leading edges between 27" and 80" from the floor, do they project less than 4" into the circulation path (objects with leading edges at or below 27" may project any amount)? If wall-mounted objects project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.2			Yes ☐ No ☐ N/A ■
3.8B	Protruding Objects	Do free-standing objects mounted on posts with leading edges between 27" and 80" high (such as a sign or telephone) overhang 12" or less above the ground or finish floor? If free-standing objects mounted on posts project into the circulation path, is the required clear width of the accessible route of travel maintained? 11B-307.3			Yes ☐ No ☐ N/A ■
3.9B	Cross Slope	Is the cross slope of the accessible route of travel no greater than 1:48? 11B-403.3			Yes ■ No ☐ N/A ☐
3.10B	Running Slope	Is the slope of the accessible route of travel no greater than 1:20, unless it complies with item 12 below? 11B-403.3	NOT THRU THE CONCRETE VALLEY GUTTER		Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room Item Name: MAIN (WEST) ENTRANCE WALKWAY TO EXTERIOR WEST PATIO AREA | ID No.: ER5 | Floor No.: | Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.11B	Running Slope	Where the slope is greater than 1:20, does it comply with the requirements for ramps? (Use Form 7 - Ramps) 11B-402.2, 11B-405			Yes ☐ No ☐ N/A ■
3.12B	Changes in Level	When walkway levels change, is the vertical distance between them less than 1/4 inch? **OR** Are changes in level between 1/4 inch and 1/2 inch beveled with a slope no greater than 1:2? 11B-303.2, 11B-303.3	NOT @ DRIVE AISLE/ VALLEY GUTTER TRANSITION		Yes ☐ No ■ N/A ☐
3.13B	Changes in Level	Are curb ramps, ramps, or elevators used for changes in level greater than 1/2 inch? (Lifts may only be used in certain limited situations) 11B-303.4			Yes ☐ No ☐ N/A ■
3.14B	Changes in Level	Are curb ramps, ramps, or elevators compliant? (Use Form 4 - Curb Ramps; Form 7 - Ramps; or Form 13 - Elevators) 11B-405, 11B-406, 11B-407			Yes ☐ No ☐ N/A ■
3.15B	Surface	Are accessible route surfaces stable, firm and slip-resistant? 11B-302.1			Yes ■ No ☐ N/A ☐
3.16B	Grates	Is the smaller dimension of a grate opening no more than 1/2 inch, and are long dimensions of rectangular gaps placed perpendicular to the usual direction of travel? 11B-302.3			Yes ☐ No ☐ N/A ■
3.17B	Abrupt Changes in Level >4"	Is the site free of abrupt changes in level adjacent to pedestrian areas exceeding 4" vertical except (1) between a walk or sidewalk and an adjacent street or driveway, or (2) where a 6" high warning curb or 42" high guard is provided to warn of a potential drop off? 11B-303.5			Yes ■ No ☐ N/A ☐
3.18B	Abrupt Changes in Level >30"	Is the site free of abrupt changes in level adjacent to pedestrian areas exceeding 30" vertical except were a 42" high guard is provided to prevent persons from falling off the open edge? See 1013.2 for exceptions.			Yes ☐ No ☐ N/A ■
3.19B	Entrance Signs	Are signs including the International Symbol of Accessibility at primary public entrances and at every major junction where the accessible route of travel diverges from the regular circulation path compliant? (Use Form 19 - Signage) 11B-216.6			Yes ☐ No ■ N/A ☐
3.20B	Directions to Accessible Entrance	When not all entrances are accessible, is there directional signage indicating the accessible route to an accessible entrance? 11B-216.6			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

EXTERIOR ROUTES OF TRAVEL (On-site Only)

Survey Form 3B

Space/Room Item Name: MAIN (WEST) ENTRANCE WALKWAY TO EXTERIOR WEST PATIO AREA	ID No.: ER5	Floor No.:	Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
3.21B	Hazardous Vehicular Areas - Detectable Warnings	If a walk crosses or adjoins the vehicular way and the walking surface is not separated by curbs, railings, or other elements between the pedestrian areas and vehicular areas, is the boundary between the areas defined by a continuous detectable warning at least 36" wide complying with 11B-705.1? (Use Form 21 - Hazards) 11B-705.1.2.5	SEE ATTACHED PICTURES		Yes ☐ No ■ N/A ☐
3.22B	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities



(ER5) ROUTE OF TRAVEL BETWEEN THE MAIN (WEST) ENTRANCE WALKWAY & THE EXTERIOR (WEST) PATIO AREA

Facility
Name: DEPARTMENT OF REHABILITATION

RESD
Project No.: 139602

Primary Entrances

CBC 11B-202.4 requires at least one primary entrance serving the primary area to be accessible. Accessible routes to these entrances must, to the maximum extent feasible, coincide with the routes for the general public and be on the shortest route from accessible parking spaces. In addition, if an entrance normally serves one or more of the functions listed below, that entrance must also be accessible. If there are multiple entrances to the facility and not all are accessible, signs shall direct to the accessible entrance.

- Public transportation stops
- Accessible parking spaces
- Passenger loading zones
- Public streets and sidewalks
- Restrooms, drinking fountains, public telephones serving the area subject to this survey

List all entrances which must be accessible in the following table and survey each of these areas with a separate copy of Survey Form 10 - Entrances. If you encounter doors, lifts, elevators, or ramps, survey that element with its specific form.

ID	Name/location of entrances (or key number on site plan)
EN1	MAIN (WEST) ENTRANCE
EN2	REAR (EAST) ENTRANCE
EN3	SOUTH EMPLOYEE USE ENTRANCE/EXIT
EN4	DEPARTMENT OF REHABILITATION SUITE 100 PUBLIC ENTRANCE/EXIT
EN5	

Note that in new construction all entrances and all ground floor exits must be fully accessible.

*Indicate the number of Survey Forms attached to Summary Sheet D in the **No**. field.*

Form	Item	No.		Form	Item	No.		Form	Item	No.
SF3	Exterior Routes (A+B)			SF7	Ramps			SF8	Stairs	1
SF10	Entrances and Exits	4		SF11	Doors and Gates			SF13	Elevators	
SF19	Signage			SF ..				SF ..		

BUILDING ENTRANCES AND EXITS

Survey Form 10

Space/Room Item Name: MAIN (WEST) ENTRANCE	Item No.: EN 1	Floor No.:	Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
10.1	Entrances Serving Site Arrival Points	Is there at least one accessible entrance connected by an accessible route to each type of existing site arrival point (i.e.: public transportation stops, accessible parking and passenger loading zones, and public streets or sidewalks)? (Use Form 3 - Exterior Routes of Travel) 11B-206.2, 11B-402			Yes ☐ No ■ N/A ☐
10.2	Entrance Sign	Are all accessible entrances identified by an ISA? 11B-216.6	ENTRANCE HAS PORTIONS NOT ACCESSIBLE		Yes ☐ No ☐ N/A ■
10.3	Directional Sign	If an entrance is not accessible, are there directional signs indicating the location of the nearest accessible entrance? 11B-216.6			Yes ☐ No ■ N/A ☐
10.4	Doors	At each accessible entrance to a building or facility, is there at least one accessible door complying with the requirements below? 11B-206.4, 11B-404			Yes ☐ No ■ N/A ☐
10.5	Clear Door Opening	When the door is open 90 degrees, is there a clear opening width at least 32" measured between the face of the door and the doorstop on the latch side? (No projections lower than 34" AFF and no more than 4" projections between 34" and 80" AFF.) 11B-404.2.5			Yes ■ No ☐ N/A ☐
10.6	Door Maneuvering Space	If the door is not automatic or power assisted, does it have maneuvering space relative to the direction of approach as shown in CBC Table 11B-11B-404.2.4.1?			Yes ■ No ☐ N/A ☐

Approach	*Side*	*Perpendicular to Door*	*Parallel to Door (beyond latch side unless noted)*
Front	Pull	60"	18"*****
Front	Push	48"	0"*
Hinge	Pull	60"	36"
Hinge	Push	44"**	22"****
Latch	Pull	60"****	24"
Latch	Push	44"****	24"

* Add 12" if closer and latch are provided.
** Add 4" if closer and latch are provided.
*** Beyond hinge side.
**** Add 4" if closer is provided.
***** Add 6" at exterior side of exterior doors.

11B-404.2.4 Fig. 11B-404.2.4.1

10.7	Door Maneuvering Space	Is the floor level (1:48) and clear within the required maneuvering space? 11B-404.2.4.4	2.8%-3.2%		Yes ☐ No ■ N/A ☐
10.8	Kick Plate	Does the bottom 10" of all doors except automatic and sliding have a smooth, uninterrupted surface on the push side to allow the door to be opened by a wheelchair footrest without creating a trap or hazardous condition? 11B-404.2.10	BRACKETS ON PUSH SIDES OF BOTH DOORS		Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
10.9	Door Threshold	Are the thresholds at doorways no higher than 1/2"? Are changes in level between 1/4" and 1/2" beveled at 1:2 or less? 11B-404.2.5, 11B-303.2, 11B-303.3			Yes ■ No ☐ N/A ☐
10.10	Door Hardware	Are all handles, locks, and latches or other operative devices operable with one hand and not require tight grasping, pinching, or twisting of the wrist? Is the operable part of the hardware 34" minimum and 44" maximum AFF? 11B-309.4, 11B-404.2.7			Yes ■ No ☐ N/A ☐
10.11	Door Operating Effort	Is the force required to operate a door no greater than 5 lbs? (Fire doors may have up to 15 lbs to achieve positive latching). 11B-309.4, 11B-404.2.9	+10# @ S DR +11# @ N DR		Yes ☐ No ■ N/A ☐
10.12	Other Door Requirements	Does the entrance door comply with all applicable requirements of Survey Form 11 - Doors and Gates? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this entrance. 11B-206.4	11.7 11.13 11.16 11.20		Yes ☐ No ■ N/A ☐
10.13	Tactile Exit Signs	At each grade level exterior exit door is there a tactile/Braille exit sign with the word "EXIT" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 1			Yes ☐ No ■ N/A ☐
10.14	Tactile Exit Signs	At each exit door leading to a grade-level exterior exit by means of a stairway or ramp, is there a tactile/Braille exit sign with the words "EXIT STAIRS DOWN (or UP)" or "EXIT RAMP DOWN (or UP)" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 2			Yes ☐ No ☐ N/A ■
10.15	Tactile Exit Signs	At each exit door that leads to a grade-level exterior exit by means of an exit enclosure that does not utilize a stair or ramp, or by means of an exit passageway, is there a tactile/Braille exit sign with the words "EXIT ROUTE" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 3 & 4, 11B-216.4.1			Yes ☐ No ☐ N/A ■
10.16	Directional Exit Signs	Is there directional signage posted at all inaccessible exits indicating the direction to the nearest accessible exit? The sign must be located so that the route does not have to be retraced, and must comply with the requirements for visual signs. 1007.10, 11B-216.6			Yes ☐ No ☐ N/A ■
10.17	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.	UNSECURED FLOOR MAT @ INTERIOR		Yes ☐ No ■ N/A ☐

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Add a quick layout sketch of the surveyed area and any additional comments below:

- ✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities



(EN1) MAIN (WEST) ENTRANCE

(EN1) MAIN (WEST) ENTRANCE

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
10.1	Entrances Serving Site Arrival Points	Is there at least one accessible entrance connected by an accessible route to each type of existing site arrival point (i.e.: public transportation stops, accessible parking and passenger loading zones, and public streets or sidewalks)? (Use Form 3 - Exterior Routes of Travel) 11B-206.2, 11B-402			Yes ☐ No ■ N/A ☐
10.2	Entrance Sign	Are all accessible entrances identified by an ISA? 11B-216.6	ENTRANCES HAVE ISA BUT ARE NOT ACCESSIBLE		Yes ☐ No ■ N/A ☐
10.3	Directional Sign	If an entrance is not accessible, are there directional signs indicating the location of the nearest accessible entrance? 11B-216.6			Yes ☐ No ■ N/A ☐
10.4	Doors	At each accessible entrance to a building or facility, is there at least one accessible door complying with the requirements below? 11B-206.4, 11B-404			Yes ☐ No ■ N/A ☐
10.5	Clear Door Opening	When the door is open 90 degrees, is there a clear opening width at least 32" measured between the face of the door and the doorstop on the latch side? (No projections lower than 34" AFF and no more than 4" projections between 34" and 80" AFF.) 11B-404.2.5			Yes ■ No ☐ N/A ☐
10.6	Door Maneuvering Space	If the door is not automatic or power assisted, does it have maneuvering space relative to the direction of approach as shown in CBC Table 11B-11B-404.2.4.1? *Approach* / *Side* / *Perpendicular to Door* / *Parallel to Door (beyond latch side unless noted)* Front / Pull / 60" / 18"****** Front / Push / 48" / 0"* Hinge / Pull / 60" / 36" Hinge / Push / 44"** / 22"*** Latch / Pull / 60"**** / 24" Latch / Push / 44"**** / 24" * Add 12" if closer and latch are provided. ** Add 4" if closer and latch are provided. *** Beyond hinge side. **** Add 4" if closer is provided. ***** Add 6" at exterior side of exterior doors. 11B-404.2.4 Fig. 11B-404.2.4.1			Yes ■ No ☐ N/A ☐
10.7	Door Maneuvering Space	Is the floor level (1:48) and clear within the required maneuvering space? 11B-404.2.4.4	5.5%		Yes ☐ No ■ N/A ☐
10.8	Kick Plate	Does the bottom 10" of all doors except automatic and sliding have a smooth, uninterrupted surface on the push side to allow the door to be opened by a wheelchair footrest without creating a trap or hazardous condition? 11B-404.2.10			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

BUILDING ENTRANCES AND EXITS

Survey Form 10

Space/Room Item Name: REAR (EAST) ENTRANCE	Item No.: EN2	Floor No.:	Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
10.9	Door Threshold	Are the thresholds at doorways no higher than 1/2"? Are changes in level between 1/4" and 1/2" beveled at 1:2 or less? 11B-404.2.5, 11B-303.2, 11B-303.3			Yes ■ No ☐ N/A ☐
10.10	Door Hardware	Are all handles, locks, and latches or other operative devices operable with one hand and not require tight grasping, pinching, or twisting of the wrist? Is the operable part of the hardware 34" minimum and 44" maximum AFF? 11B-309.4, 11B-404.2.7			Yes ■ No ☐ N/A ☐
10.11	Door Operating Effort	Is the force required to operate a door no greater than 5 lbs? (Fire doors may have up to 15 lbs to achieve positive latching). 11B-309.4, 11B-404.2.9	15 #'s EA DR		Yes ☐ No ■ N/A ☐
10.12	Other Door Requirements	Does the entrance door comply with all applicable requirements of Survey Form 11 - Doors and Gates? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this entrance. 11B-206.4	11.7 11.13 11.14 NORTH DR 11.20		Yes ☐ No ■ N/A ☐
10.13	Tactile Exit Signs	At each grade level exterior exit door is there a tactile/Braille exit sign with the word "EXIT" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 1			Yes ☐ No ■ N/A ☐
10.14	Tactile Exit Signs	At each exit door leading to a grade-level exterior exit by means of a stairway or ramp, is there a tactile/Braille exit sign with the words "EXIT STAIRS DOWN (or UP)" or "EXIT RAMP DOWN (or UP)" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 2			Yes ☐ No ☐ N/A ■
10.15	Tactile Exit Signs	At each exit door that leads to a grade-level exterior exit by means of an exit enclosure that does not utilize a stair or ramp, or by means of an exit passageway, is there a tactile/Braille exit sign with the words "EXIT ROUTE" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 3 & 4, 11B-216.4.1			Yes ☐ No ☐ N/A ■
10.16	Directional Exit Signs	Is there directional signage posted at all inaccessible exits indicating the direction to the nearest accessible exit? The sign must be located so that the route does not have to be retraced, and must comply with the requirements for visual signs. 1007.10, 11B-216.6			Yes ☐ No ■ N/A ☐
10.17	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.	UNSECURED FLOOR MAT @ INTERIOR		Yes ☐ No ■ N/A ☐

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Space/Room Item Name: REAR (EAST) ENTRANCE	Item No.: EN2	Floor No.:	Project No.: 139602

Add a quick layout sketch of the surveyed area and any additional comments below:

- ✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

(EN2) REAR (EAST) ENTRANCE

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
10.1	Entrances Serving Site Arrival Points	Is there at least one accessible entrance connected by an accessible route to each type of existing site arrival point (i.e.: public transportation stops, accessible parking and passenger loading zones, and public streets or sidewalks)? (Use Form 3 - Exterior Routes of Travel) 11B-206.2, 11B-402			Yes ☐ No ■ N/A ☐
10.2	Entrance Sign	Are all accessible entrances identified by an ISA? 11B-216.6			Yes ☐ No ■ N/A ☐
10.3	Directional Sign	If an entrance is not accessible, are there directional signs indicating the location of the nearest accessible entrance? 11B-216.6			Yes ☐ No ■ N/A ☐
10.4	Doors	At each accessible entrance to a building or facility, is there at least one accessible door complying with the requirements below? 11B-206.4, 11B-404			Yes ☐ No ■ N/A ☐
10.5	Clear Door Opening	When the door is open 90 degrees, is there a clear opening width at least 32" measured between the face of the door and the doorstop on the latch side? (No projections lower than 34" AFF and no more than 4" projections between 34" and 80" AFF.) 11B-404.2.5			Yes ■ No ☐ N/A ☐
10.6	Door Maneuvering Space	If the door is not automatic or power assisted, does it have maneuvering space relative to the direction of approach as shown in CBC Table 11B-11B-404.2.4.1? *Approach* / *Side* / *Perpendicular to Door* / *Parallel to Door (beyond latch side unless noted)* Front / Pull / 60" / 18"***** Front / Push / 48" / 0"* Hinge / Pull / 60" / 36" Hinge / Push / 44"** / 22"*** Latch / Pull / 60"**** / 24" Latch / Push / 44"**** / 24" * Add 12" if closer and latch are provided. ** Add 4" if closer and latch are provided. *** Beyond hinge side. **** Add 4" if closer is provided. ***** Add 6" at exterior side of exterior doors. 11B-404.2.4 Fig. 11B-404.2.4.1	PULL SIDE LATCH <24" PUSH SIDE <48"&44"		Yes ☐ No ■ N/A ☐
10.7	Door Maneuvering Space	Is the floor level (1:48) and clear within the required maneuvering space? 11B-404.2.4.4			Yes ■ No ☐ N/A ☐
10.8	Kick Plate	Does the bottom 10" of all doors except automatic and sliding have a smooth, uninterrupted surface on the push side to allow the door to be opened by a wheelchair footrest without creating a trap or hazardous condition? 11B-404.2.10			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
10.9	Door Threshold	Are the thresholds at doorways no higher than 1/2"? Are changes in level between 1/4" and 1/2" beveled at 1:2 or less? 11B-404.2.5, 11B-303.2, 11B-303.3	> 1/2"		Yes ☐ No ■ N/A ☐
10.10	Door Hardware	Are all handles, locks, and latches or other operative devices operable with one hand and not require tight grasping, pinching, or twisting of the wrist? Is the operable part of the hardware 34" minimum and 44" maximum AFF? 11B-309.4, 11B-404.2.7			Yes ■ No ☐ N/A ☐
10.11	Door Operating Effort	Is the force required to operate a door no greater than 5 lbs? (Fire doors may have up to 15 lbs to achieve positive latching). 11B-309.4, 11B-404.2.9	+10#		Yes ☐ No ■ N/A ☐
10.12	Other Door Requirements	Does the entrance door comply with all applicable requirements of Survey Form 11 - Doors and Gates? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this entrance. 11B-206.4	11.6 11.10 11.13 11.14 11.21		Yes ☐ No ■ N/A ☐
10.13	Tactile Exit Signs	At each grade level exterior exit door is there a tactile/Braille exit sign with the word "EXIT" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 1			Yes ☐ No ☐ N/A ■
10.14	Tactile Exit Signs	At each exit door leading to a grade-level exterior exit by means of a stairway or ramp, is there a tactile/Braille exit sign with the words "EXIT STAIRS DOWN (or UP)" or "EXIT RAMP DOWN (or UP)" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 2			Yes ☐ No ■ N/A ☐
10.15	Tactile Exit Signs	At each exit door that leads to a grade-level exterior exit by means of an exit enclosure that does not utilize a stair or ramp, or by means of an exit passageway, is there a tactile/Braille exit sign with the words "EXIT ROUTE" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 3 & 4, 11B-216.4.1			Yes ☐ No ☐ N/A ■
10.16	Directional Exit Signs	Is there directional signage posted at all inaccessible exits indicating the direction to the nearest accessible exit? The sign must be located so that the route does not have to be retraced, and must comply with the requirements for visual signs. 1007.10, 11B-216.6			Yes ☐ No ■ N/A ☐
10.17	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.	ENTRANCE/EXIT STAIRS - SEE FOLLOWING SHEETS		Yes ☐ No ■ N/A ☐

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Add a quick layout sketch of the surveyed area and any additional comments below:

- ✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

STAIRS

Survey Form 8

Space/Room Item Name: SOUTH EXIT EXTERIOR STAIRS

Item No.: EN3

Floor No.:

Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
8.1	Stairs	Do public and common use interior and exterior stairs comply with the accessibility requirements below? 11B-210.1, 11B-504			Yes ☐ No ■ N/A ☐
8.2	Risers/Treads	Are the risers closed? 11B-504.3			Yes ■ No ☐ N/A ☐
8.3	Risers/Treads	Are the treads uniform and at least 11" wide measured from riser to riser and are the risers all uniform and between 4" and 7" in height? 1009.7.2, 11B-504.2			Yes ■ No ☐ N/A ☐
8.4	Color Strip Interior Stairs	Is there a solid contrasting color stripe 2" wide to a maximum of 4" wide parallel to and not more than 1" away from the nosing extending the full width of the step on the upper approach and the lower thread of the stairway? 11B-504.4.1			Yes ☐ No ■ N/A ☐
8.5	Color Strip Exterior Stairs	Is there a solid contrasting color stripe 2" wide to a maximum of 4" wide parallel to and not more than 1" away from the nosing extending the full width of the step on the upper approach and all threads of the stairway? 11B-504.4.1			Yes ☐ No ■ N/A ☐
8.6	Nosings 2007-2013	Do stair nosings project no more than 1-1/4" past the face of the riser below? Is the transition from the nosing to the riser free of abrupt edges? (The 2007 CBC requires that stair nosings project no more than 1-1/4". The 2001, 1998 & 1995 CBC required that stair nosings project no more than 1-1/2". There is no requirement to retroactively alter existing nosing projections of 1-1/2" when constructed in compliance with the building code in effect at the time of original construction.) 1009.7.5.1, 11B-504.5			Yes ■ No ☐ N/A ☐
8.7	Continuous Handrails	Are there continuous handrails along both sides? 11B-505.2			Yes ☐ No ■ N/A ☐
8.8	Handrails	On dogleg or switchback stairs, is the inside handrail continuous at landings? 11B-505.3			Yes ☐ No ☐ N/A ■
8.9	Handrail Extensions	Do the handrails extend a min. of 12" beyond the top nosing and 12" plus the tread width, beyond the bottom nosing, and are the tops of handrails between 34" and 38" above the stair nosings? 11B-505.10.2, 11B-505.10.3, 11B-505.4			Yes ☐ No ■ N/A ☐
8.10	Diameter and Clearance	Is the diameter of the handrail between 1-1/4" and 2" in cross-sectional nominal dimension or for non-circular handrails is the perimeter 4" minimum and 6 ¼" maximum and the cross-section 2 ¼" maximum, and is the clear space between handrails and walls 1-1/2" minimum? 11B-505.5, 11B-505.7.1, 11B-505.7.2			Yes ■ No ☐ N/A ☐
8.11	Stairway Width	Are stairways serving an area of rescue assistance at least 48" wide between handrails (unless building is sprinklered)? 1007.3, 1007.6			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
8.12	Hazards	Are handrail edges free of sharp or abrasive elements and shall have rounded edges? 11B-505.8	SEE PICS		Yes ☐ No ■ N/A ☐
8.13	Wet Conditions	Are the stair treads and landings designed to prevent the accumulation of water? 11B-504.7			Yes ■ No ☐ N/A ☐
8.14	Floor Identification	Is there a floor identification sign at each landing to identify the floor level complying with signage requirements? At the exit discharge, does the sign include a raised five pointed star located to the left of the identifying floor level? 11B-504.8, 11B-703.1, 11B-703.2, 11B-703.3, 11B-703.5			Yes ☐ No ■ N/A ☐
8.15	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add any additional comments below:

- ✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities





(EN3) SOUTH EMPLOYEE USE ENTRANCE/EXIT & SOUTH EXIT EXTERIOR STAIRS



(EN3) SOUTH EMPLOYEE USE ENTRANCE/EXIT & SOUTH EXIT EXTERIOR STAIRS

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
10.1	Entrances Serving Site Arrival Points	Is there at least one accessible entrance connected by an accessible route to each type of existing site arrival point (i.e.: public transportation stops, accessible parking and passenger loading zones, and public streets or sidewalks)? (Use Form 3 - Exterior Routes of Travel) 11B-206.2, 11B-402			Yes ☐ No ■ N/A ☐
10.2	Entrance Sign	Are all accessible entrances identified by an ISA? 11B-216.6	SUITE 100 DOOR		Yes ■ No ☐ N/A ☐
10.3	Directional Sign	If an entrance is not accessible, are there directional signs indicating the location of the nearest accessible entrance? 11B-216.6			Yes ☐ No ☐ N/A ■
10.4	Doors	At each accessible entrance to a building or facility, is there at least one accessible door complying with the requirements below? 11B-206.4, 11B-404	SEE 10.12		Yes ☐ No ■ N/A ☐
10.5	Clear Door Opening	When the door is open 90 degrees, is there a clear opening width at least 32" measured between the face of the door and the doorstop on the latch side? (No projections lower than 34" AFF and no more than 4" projections between 34" and 80" AFF.) 11B-404.2.5			Yes ■ No ☐ N/A ☐
10.6	Door Maneuvering Space	If the door is not automatic or power assisted, does it have maneuvering space relative to the direction of approach as shown in CBC Table 11B-11B-404.2.4.1?	DOOR HAS AUTO. DOOR OPENER		Yes ☐ No ☐ N/A ■

Approach	*Side*	*Perpendicular to Door*	*Parallel to Door (beyond latch side unless noted)*
Front	Pull	60"	18"*****
Front	Push	48"	0"*
Hinge	Pull	60"	36"
Hinge	Push	44"**	22"***
Latch	Pull	60"****	24"
Latch	Push	44"****	24"

* Add 12" if closer and latch are provided.
** Add 4" if closer and latch are provided.
*** Beyond hinge side.
**** Add 4" if closer is provided.
***** Add 6" at exterior side of exterior doors.

11B-404.2.4 Fig. 11B-404.2.4.1

10.7	Door Maneuvering Space	Is the floor level (1:48) and clear within the required maneuvering space? 11B-404.2.4.4			Yes ■ No ☐ N/A ☐
10.8	Kick Plate	Does the bottom 10" of all doors except automatic and sliding have a smooth, uninterrupted surface on the push side to allow the door to be opened by a wheelchair footrest without creating a trap or hazardous condition? 11B-404.2.10			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Space/Room Item Name: DEPT. OF REHABILITATION SUITE 100 PUBLIC ENTRANCE | Item No.: EN 4 | Floor No.: | Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
10.9	Door Threshold	Are the thresholds at doorways no higher than 1/2"? Are changes in level between 1/4" and 1/2" beveled at 1:2 or less? 11B-404.2.5, 11B-303.2, 11B-303.3			Yes ■ No ☐ N/A ☐
10.10	Door Hardware	Are all handles, locks, and latches or other operative devices operable with one hand and not require tight grasping, pinching, or twisting of the wrist? Is the operable part of the hardware 34" minimum and 44" maximum AFF? 11B-309.4, 11B-404.2.7			Yes ■ No ☐ N/A ☐
10.11	Door Operating Effort	Is the force required to operate a door no greater than 5 lbs? (Fire doors may have up to 15 lbs to achieve positive latching). 11B-309.4, 11B-404.2.9	DOOR HAS AUTO DOOR OPENER		Yes ☐ No ■ N/A ☐
10.12	Other Door Requirements	Does the entrance door comply with all applicable requirements of Survey Form 11 - Doors and Gates? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this entrance. 11B-206.4	11.18 11.19 11.23 11.27		Yes ☐ No ■ N/A ☐
10.13	Tactile Exit Signs	At each grade level exterior exit door is there a tactile/Braille exit sign with the word "EXIT" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 1			Yes ☐ No ☐ N/A ■
10.14	Tactile Exit Signs	At each exit door leading to a grade-level exterior exit by means of a stairway or ramp, is there a tactile/Braille exit sign with the words "EXIT STAIRS DOWN (or UP)" or "EXIT RAMP DOWN (or UP)" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 2			Yes ☐ No ☐ N/A ■
10.15	Tactile Exit Signs	At each exit door that leads to a grade-level exterior exit by means of an exit enclosure that does not utilize a stair or ramp, or by means of an exit passageway, is there a tactile/Braille exit sign with the words "EXIT ROUTE" mounted on the wall adjacent to the latch side of the door? 1011.4 Item 3 & 4, 11B-216.4.1			Yes ☐ No ■ N/A ☐
10.16	Directional Exit Signs	Is there directional signage posted at all inaccessible exits indicating the direction to the nearest accessible exit? The sign must be located so that the route does not have to be retraced, and must comply with the requirements for visual signs. 1007.10, 11B-216.6			Yes ☐ No ☐ N/A ■
10.17	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Space/Room Item Name: DEPT. OF REHABILITATION SUITE 100 PUBLIC ENTRANCE | Item No.: EN4 | Floor No.: | Project No.: 139602

Add a quick layout sketch of the surveyed area and any additional comments below:

- ✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities



(EN4) DEPARTMENT OF REHABILITATION SUITE 100
PUBLIC ENTRANCE

Facility
Name: DEPARTMENT OF REHABILITATION

RESD
Project No.: 139602

Interior Routes of Travel

An accessible route of travel must connect the accessible building or facility entrances with all accessible spaces of the primary area and its key facilities. Accessible routes must, to the maximum extent feasible, coincide with the routes for the general public. If accessible connections do not exist between these elements, that is a violation. If accessible routes do exist then the completed survey will reveal their satisfactory and unsatisfactory features.

If the primary area or any of its key facilities is located on a level other than the ground floor level, an accessible elevator must provide access to that level. State leased facilities cannot take the existing elevator exception. Note that the use of platform lifts to provide accessibility is very limited in state-leased facilities. **Common and public use stairways must be compliant. Stairs used solely for emergency egress must be surveyed and meet current California Building Code.** Doorways (including signage) leading to an emergency staircase must be fully accessible.

List all corridors, hallways, and lobbies which must be accessible in the following table and survey each of these areas with a separate copy of Survey Form 12 - Lobbies and Corridors. If you encounter elevators, ramps, lifts, stairs, public telephones, or drinking fountains, survey that element with its specific survey form:

ID	Name/location of routes of travel (or key number on site plan)	On floor
IR1	BUILDING LOBBY	
IR2	DEPARTMENT OF REHABILITATION RECEPTION AREA	
IR3	DEPARTMENT OF REHABILITATION HALLWAY	
IR4		
IR5		
IR6		
IR7		
IR8		
IR9		
IR10		

*Indicate the number of Survey Forms attached to Summary Sheet E in the **No**. field.*

Form	Item	No.		Form	Item	No.		Form	Item	No.
SF5	Drinking Fountains	1		SF6	Telephones			SF7	Ramps	
SF8	Stairs			SF9	Platform Lifts			SF11	Doors and Gates	1
SF12	Lobbies and Corridors	3		SF13	Elevators			SF19	Signage	
SF20	Alarms			SF ..				SF ..		

BUILDING LOBBIES AND CORRIDORS (Interior Accessible Route) — Survey Form 12A

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
BUILDING LOBBY	1R1		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
12.1A	Accessible Route	Is there an accessible route of travel connecting accessible entrances with all accessible elements and spaces within the building or facility, including mezzanines? 11B-206.2.4, 11B-402			Yes ■ No ☐ N/A ☐
12.2A	Width - General	Is the accessible route of travel, except at doorways, at least 44" wide where the occupancy load is ≥ 10, or at least 36" where the occupancy load is <10? 11B-403.5.1, 11N-403.5.3			Yes ■ No ☐ N/A ☐
12.3A	U-Turn	Where the accessible route of travel makes a U-turn around an obstacle which is less than 48" wide, is the accessible route at least 42" wide on the approaches and 48" wide in the turn? or Where the accessible route of travel makes a U-turn around an obstacle which is less than 60", is the accessible route at least 36" wide on the approaches and 60" wide in the turn? 11B-403.5.2, Fig. 11B-403.5.2			Yes ☐ No ☐ N/A ■
12.4A	Floor Surface	Are the floor surfaces on the accessible route of travel stable, firm, and slip-resistant? 11B-403.2, 11B-302			Yes ■ No ☐ N/A ☐
12.5A	Clear Door Opening	When the door is open 90 degrees, is there a clear opening width at least 32" measured between the face of the door and the doorstop on the latch side? Are projections into the clear opening width between 34" and 80" AFF not exceeding 4"? (Check the N/A box if doors are being documented by another portion of your survey.)11B-206.4, 11B-404.2.3			Yes ☐ No ☐ N/A ■
12.6A	Door Maneuvering Space	If the door is not automatic or power assisted, does it have maneuvering space relative to the direction of approach as shown in CBC Table11B-404.2.4.1?			Yes ☐ No ☐ N/A ■

Approach	*Side*	*Perpendicular to Door*	*Parallel to Door (beyond latch side unless noted)*
Front	Pull	60"	18"*****
Front	Push	48"	0"*
Hinge	Pull	60"	36"
Hinge	Push	44"**	22"***
Latch	Pull	60"****	24"
Latch	Push	44"****	24"

* Add 12" if closer and latch are provided.
** Add 4" if closer and latch are provided.
*** Beyond hinge side.
**** Add 4" if closer is provided.
***** Add 6" at exterior side of exterior doors.

11B-404.2.4, 11B-404.2.3

12.7A	Door Hardware	Are all handles, locks, and latches or other operative devices operable with one hand? 11B-309.4, 11B-404.2.7			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

BUILDING LOBBIES AND CORRIDORS (Interior Accessible Route) — Survey Form 12A

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
BUILDING LOBBY	1R1		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
12.8A	Door Operating Effort	Is the force required to operate a door no greater than 5 lbs? (Fire doors may have up to 15 lbs to achieve positive latching). 11B-404.2.9			Yes ☐ No ☐ N/A ■
12.9A	Revolving Door	If a revolving door or turnstile is used on an accessible route, is an accessible door or gate provided adjacent to the revolving door or turnstile to facilitate the same use pattern? 11B-206.3, 11B-404.3.1			Yes ☐ No ☐ N/A ■
12.10A	Other Door Requirements	Does the door comply with all applicable requirements of Survey Form 11 - Doors and Gates? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this interior accessible route. 11B-206.4			Yes ☐ No ☐ N/A ■
12.11A	Directional and Informational Signs	Do signs which provide direction to, or information about, functional spaces of the building interior and exterior comply with the requirement for visual signage? EXCEPTION: Building directories, menus, and all other signs which are temporary are not required to comply. 11B-216.3, 11B.703.5	JANITOR & ELEVATOR EQUIPMENT		Yes ☐ No ■ N/A ☐
12.12A	Room/Space Identification Signs	Do signs which identify permanent rooms and spaces comply with the visual and tactile/Braille requirements below? (Check the N/A box if room identification signs are being documented by another portion of your survey.) 11B-216.2, 11B-703.1, 11B-703.2, 11B-703.3			Yes ☐ No ☐ N/A ■
12.13A	Tactile Exit Signs	At each grade level exterior exit door is there a tactile/Braille exit sign with the word "EXIT" mounted on the wall adjacent to the latch side of the door? 1011.4 item 1	SEE SUMMARY SHEET D		Yes ☐ No ■ N/A ☐
12.14A	Tactile Exit Signs	At each exit door leading to a grade-level exterior exit by means of a stairway or ramp, is there a tactile/Braille exit sign with the words "EXIT STAIRS DOWN (or UP)" or "EXIT RAMP DOWN (or UP)" mounted on the wall adjacent to the latch side of the door? 1011.4 item 2			Yes ☐ No ☐ N/A ■
12.15A	Tactile Exit Signs	At each exit door that leads to a grade-level exterior exit by means of an exit enclosure that does not utilize a stair or ramp, or by means of an exit passageway, is there a tactile/Braille exit sign with the words "EXIT ROUTE" mounted on the wall adjacent to the latch side of the door? 1011.4 item 3			Yes ☐ No ☐ N/A ■
12.16A	Side of Doors	Are permanent identification signs located on the approach side of the door as one enters the room or space? Are exit signs located on the approach side of the door as one exits the room or space? 11B-216.2, 11B-216.4, 11B-703.4.2			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

BUILDING LOBBIES AND CORRIDORS (Interior Accessible Route) — Survey Form 12A

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
BUILDING LOBBY	1R1		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
12.17A	Mounting Location (Visual/Tactile Signs)	Are tactile signs mounted on the wall adjacent to the latch side of the door 48" min from baseline of lowest Braille to 60" max AFF from baseline of highest line of raised characters? For double doors with one active leaf, is the sign located on the inactive leaf? For double doors with both active leafs, is the sign located to the right of the right hand door? If there is no wall space, is the sign located at the latch side of a single door or at the right side of double door on the nearest adjacent wall? 11B-703.4.1 Figure 11B-703.4.1, 11B-703.4.2			Yes ☐ No ☐ N/A ■
12.18A	Approach (Visual/Tactile Signs)	Is there a clear floor space of 18"min x 18"min, centered on the tactile characters, beyond the arc of any door swing between the closed position and 45 degree open position? 11B-703.4.2			Yes ☐ No ☐ N/A ■
12.19A	Tactile and Braille Characters	Are the characters on tactile signs accompanied by Grade 2 Braille? Are the Braille dots domed or rounded shape and is the Braille placed a min. of 3/8" and a max. of 1/2" below the tactile characters, flush left or centered and 3/8" minimum from raised borders and decorative elements? If the tactile text is multi-lined, is all Braille placed together below all lines of tactile text? Are the dots within each Braille cell 1/10" o.c.? 11B-703.3, 11B-703.3.1, 11B-703.3.2, Table 11B-703.3.1	SEE SUMMARY SHEET D		Yes ☐ No ■ N/A ☐
12.20A	Character Size	Are the raised characters on tactile signs between 5/8" and 2" high and raised at least 1/32"? 11B-703.2.1, 11B-703.2.5			Yes ■ No ☐ N/A ☐
12.21A	Upper Case	Are the raised characters on tactile signs upper case, and sans serif or simple serif? 11B-703.2.2, 11B-703.2.3			Yes ■ No ☐ N/A ☐
12.22A	Contrast	Do the characters on signs contrast with their background (light-on-dark or dark-on-light) and do the signs have a non-glare finish? 11B-703.5, 11B-703.6.2, 11B-703.7.1			Yes ■ No ☐ N/A ☐
12.23A	Other Identification Signage Requirements	Does the sign comply with all applicable requirements of Survey Form 19 - Signage? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this entrance. 11B-703			Yes ☐ No ☐ N/A ■
12.24A	Counter Height	At reception, transaction, or security counters, is there a portion of the main counter at least 36" long and 28" minimum and 34" maximum high? 11B-226.1, 11B-902.3			Yes ☐ No ☐ N/A ■
12.25A	Counter Knee Space	Where seated service at a counter is provided, is the knee space at least 27" high, 30" wide, and 19" deep? 11B-306.2.3 exception. 2, 11B-306.3.3 exception 2			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

BUILDING LOBBIES AND CORRIDORS (Interior Accessible Route) — Survey Form 12A

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
BUILDING LOBBY	1R1		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
12.26A	Changes in Level	Are ramps or elevators used for changes in level greater than 1/2"? (Platform lifts may only be used in certain limited situations.) 11B-303.4			Yes ☐ No ☐ N/A ■
12.27A	Protruding Objects	If objects mounted to the wall have leading edges between 27 and 80" from the floor, do they project less than 4" into the circulation path? (Wall mounted objects with leading edges at or below 27" may project any amount so long as the required clear width of an accessible route is not reduced.) If a guardrail or barrier is provided, is it maximum 27"AFF? 11B-307.2, 11B-307.3, 11B-307.4			Yes ■ No ☐ N/A ☐
12.28A	Head room	Is there at least 80" clear head room within the pedestrian circulation area, including the accessible route of travel? 11B-307.4			Yes ■ No ☐ N/A ☐
12.29A	Alarms	If emergency warning systems are provided, do they include both audible alarms and visual alarms complying with Survey Form 20 - Alarms? 907.5.2.1 (Audible), 907.5.2.3 (Visible), 11B-215			Yes ☐ No ☐ N/A ■
12.30A	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.	OPERABLE PART OF FIRE EXTINGUISHER — >48"		Yes ☐ No ■ N/A ☐

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

DRINKING FOUNTAINS

Survey Form 5

Space/Room: BUILDING LOBBY
Item Name: DRINKING FOUNTAIN

Item No.:

Floor No.:

Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Comments	Lessor/Architect Comments	Check
5.1	Drinking Fountains	Are there two drinking fountains on each floor and is there one drinking fountain accessible to wheelchair users and one accessible to persons who have difficulty bending or stooping (e.g. 'hi-lo' drinking fountain)? 11B-211.2	ONLY ONE WHEELCHAIR ACCESSIBLE DRINKING FOUNTAIN		Yes ☐ No ■ N/A ☐
5.2	Drinking Fountains	Where there is more than two drinking fountains on a floor, are 50% wheelchair accessible and 50% accessible to persons who have difficulty bending or stooping? 11B-211.3			Yes ☐ No ☐ N/A ■
5.3	Accessible Route	Is the accessible drinking fountain on an accessible route? 11B-211.2			Yes ■ No ☐ N/A ☐
5.4	Depth	Is the drinking fountain a minimum of 18 inches and a maximum of 19 inches in depth? 11B-602.8			Yes ■ No ☐ N/A ☐
5.5	Knee Space	Is the knee clearance between the bottom of the apron and the floor at least 27" high, 30" wide, and 8" deep, the depth being taken from the front edge of the fountain back towards the wall or post? 11B-602.2, 11B-306.3.3			Yes ■ No ☐ N/A ☐
5.6	Toe Space	Is the toe clearance at least 9" high and 17" deep from the front edge of the fountain? 11B-306.2.3			Yes ■ No ☐ N/A ☐
5.7	Clear Floor Space	Is there a clear floor space at least 30" by 48" providing a forward approach (a side approach is not acceptable)? 11B-602.2, 11B-305			Yes ■ No ☐ N/A ☐
5.8	Protruding Objects	If a wall-mounted drinking fountain has a leading edge between 27" and 80" from the floor, does it project less than 4 inches into the circulation path? 11B-307.2			Yes ■ No ☐ N/A ☐
5.9	Pedestrian Protection	Is the drinking fountain located completely within an alcove or wing walls that don't encroach into pedestrian ways? Is the alcove 32" wide by 18" deep minimum (for single) and project as far as the drinking fountain and to within 6" vertically from the floor? 11B-602.9			Yes ■ No ☐ N/A ☐
5.10	Spout Height	Is the bubbler outlet no higher than 36" above the floor and is the water flow at least 4" high to allow the insertion of a cup under the flow of water? 11B-602.4, 11B-602.6	WATER FLOW < 4" HIGH		Yes ☐ No ■ N/A ☐
5.11	Location	Is the bubbler outlet located 15" minimum from the vertical support and 5" maximum from the front edge of the unit, including bumpers, with a water flow trajectory parallel or nearly parallel to the front edge? 11B-602.5			Yes ■ No ☐ N/A ☐
5.12	Water Flow	If the spout is within 3" of the front edge of the fountain the angle of the water stream shall be 30 degrees minimum and if the spout is between 3" and 5" from the front of the unit, the angle of the water stream shall be 15 degrees maximum? 11B-602.6			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

DRINKING FOUNTAINS

Survey Form 5

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
BUILDING LOBBY DRINKING FOUNTAIN			139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Comments	Lessor/Architect Comments	Check
5.13	Controls Location Operable Parts	Are the controls front-mounted or on the side located within 6" of the front edge? 11B-602.3			Yes ■ No ☐ N/A ☐
5.14	Operation	Are the controls operable with one hand, and without tight grasping, pinching, or twisting of the wrist, and is the force to operate the controls no greater than 5 lbs? 11B-309.4			Yes ■ No ☐ N/A ☐
5.15	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

DEPARTMENT OF REHABILITATION – 4930 W KAWEAH COURT SUITE 100, VISALIA, CA 93277



FLOOR PLAN NTS

(IR1) BUILDING LOBBY

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
12.1B	Accessible Route	Is there an accessible route of travel connecting accessible building entrances with the state agency's lobby, reception, or public waiting area? 11B-206, 11B-402			Yes ■ No ☐ N/A ☐
12.2B	Directional and Informational Signs	Do signs which provide direction to, or information about, functional spaces of the building comply with the requirement for visual signage? EXCEPTION: Building directories, menus, and all other signs which are temporary are not required to comply. 11B-216.3, 11B-703.5	SUITE 100 SIGNS DO NOT MEET THE REQUIREMENTS		Yes ☐ No ■ N/A ☐
12.3B	Room/Space Identification Signs	Do signs which identify permanent rooms and spaces comply with the visual and tactile/Braille requirements below? (Check the N/A box if room identification signs are being documented by another portion of your survey.) 11B-216.2, 11B-703.1, 11B-703.2, 11B-703.3			Yes ☐ No ■ N/A ☐
12.4B	Mounting Location	Are tactile signs mounted on the wall adjacent to the latch side of the door 48" min from baseline of lowest Braille to 60" max AFF from baseline of highest line of raised characters? For double doors with one active leaf, is the sign located on the inactive leaf? For double doors with both active leafs, is the sign located to the right of the right hand door? If there is no wall space, is the sign located at the latch side of a single door or at the right side of double door on the nearest adjacent wall? 11B-703.4.1 Figure 11B-703.4.1, 11B-703.4.2			Yes ☐ No ■ N/A ☐
12.5B	Approach	Is there a clear floor space 18"x18" minimum, centered on the tactile characters, beyond the arc of any door swing between the closed position and 45° open position? 11B-703.4.2			Yes ■ No ☐ N/A ☐
12.6B	Raised and Braille Characters	Are the characters on tactile signs accompanied by Grade 2 Braille? Are the Braille dots domed or rounded shape and is the Braille placed a min. of 3/8" and a max. of 1/2" below the tactile characters, flush left or centered and 3/8" minimum from raised borders and decorative elements? If the tactile text is multi-lined, is all Braille placed together below all lines of tactile text? Are the dots within each Braille cell 1/10" o.c.? 11B-703.3, 11B-703.3.1, 11B-703.3.2, Table 11B-703.3.1	BRAILLE IS NOT GRADE 2		Yes ☐ No ■ N/A ☐
12.7B	Character Size	Are the raised characters on tactile signs between 5/8" and 2" high and raised at least 1/32"? 11B-703.2.1, 11B-703.2.5, Figure 11B-703.7.1			Yes ■ No ☐ N/A ☐
12.8B	Upper Case	Are the raised characters on tactile signs upper case, and sans serif or simple serif? 11B-703.2.2, 11B-703.2.3			Yes ■ No ☐ N/A ☐
12.9B	Contrast	Do the characters and/or pictograms on signs contrast with their background (light-on-dark or dark-on-light) and do the signs have a non-glare finish? 11B-703.5.1, 11B-703.6.2, 11B-703.7.1			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
12.10B	Counter Height	At reception, transaction, or security counters, is there a portion of the main counter at least 36" long and 28" minimum and 34" maximum high? 11B-226.1, 11B-902.3			Yes ■ No ☐ N/A ☐
12.11B	Counter Knee Space	Where seated service at counter is provided, is the knee space at least 27" high, 30" wide, and 19" deep? 11B-306.2.3 exception 2, 11B-306.3.3 exception 2			Yes ☐ No ☐ N/A ■
12.12B	Public Address System	If the public address systems convey audible information to the public, does it also give it in visual format? 11B-810.7			Yes ☐ No ☐ N/A ■
12.13B	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ■ N/A ☐

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add any additional comments below:

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

- THE RECEPTION/WAITING AREA DOES NOT HAVE A CLEAR FLOOR SPACE ADJACENT TO THE CHAIRS FOR INDIVIDUALS IN WHEELCHAIRS.

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

DOORS AND GATES

Survey Form 11

Space/Room Item Name: DOOR TO/FROM RECEPTION AREA & HALLWAY

Item No.: 1R2/1R3

Floor No.:

Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
11.1	Accessible Spaces	Do all doors, doorways, or gate serving rooms and spaces comply with the requirements below? 11B-206.5.2, 11B-404			Yes ☐ No ■ N/A ☐
11.2	Accessible Routes	Does each door that is an element of an accessible route comply with the requirements below? 11B-206.5, 11B-404			Yes ☐ No ■ N/A ☐
11.3	Revolving Doors and Turnstiles	If a revolving door or turnstile is used on an accessible route, is an accessible door or gate provided adjacent to the turnstile or revolving door to facilitate the same use pattern? 11B-206.3, 11B-404.2.1, 11B-404.3.7			Yes ☐ No ☐ N/A ■
11.4	Gates	Do gates, including ticket gates, meet all applicable specifications of doors? 11B-206.5			Yes ☐ No ☐ N/A ■
11.5	Clear Opening	When a door is open 90 degrees, is there a clear opening width at least 32" measured between the face of the door and the door stop on the latch side? At double doors does at least one door leaf comply? 11B-404.2.3, 11B-404.2.2			Yes ■ No ☐ N/A ☐
11.6	Door Maneuvering Space	If the door is not automatic or power assisted, does it have maneuvering space relative to the direction of approach as shown in CBC Table11B-404.2.4.1	FURNITURE OBSTRUCTS MANEUVERING SPACES		Yes ☐ No ■ N/A ☐

Approach	*Side*	*Perpendicular to Door*	*Parallel to Door (beyond latch side unless noted)*
Front	Pull	60"	18"*****
Front	Push	48"	0"*
Hinge	Pull	60"	36"
Hinge	Push	44"**	22"***
Latch	Pull	60"****	24"
Latch	Push	44"****	24"

* Add 12" if closer and latch are provided.
** Add 4" if closer and latch are provided.
*** Beyond hinge side.
**** Add 4" if closer is provided.
***** Add 6" at exterior side of exterior doors.

11B-404.2.4, 11B-404.2.4.3

11.7	Maneuvering Space	Is the floor level (1:48 max) and clear within the required maneuvering space? 11B-404.2.4.4			Yes ■ No ☐ N/A ☐
11.8	Vestibules - Doors in Series	If there are two doors in a series, is the clear space between doors in a vestibule at least 48" plus the width of any door swinging into the space? 11B-404.2.6, Figure 11B-404.2.6			Yes ☐ No ☐ N/A ■
11.9	Vestibules - Doors in Series	Do doors in a series swing in the same direction? **OR** Do they swing away from the space between the doors? 11B-404.2.6			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
11.10	Thresholds	Are the thresholds at doorways no higher than 1/2"? Are changes in level between 1/4" and 1/2" beveled at 1:2 or less? 11B-404.2.5,11B-303.2, 11B-303.3			Yes ■ No ☐ N/A ☐
11.11	Hardware	Are all handles, locks, and latches or other operative devices operable with one hand, and are they operable without tight grasping, pinching, or twisting of the wrist? (Levers and push/pull type mechanisms are acceptable designs.) 11B-404.2.7, 11B-309.4			Yes ■ No ☐ N/A ☐
11.12	Hardware	Is the operating hardware mounted between 34" and 44" AFF? 11B-404.2.7, 11B-309.4			Yes ■ No ☐ N/A ☐
11.13	Door Operating Effort	Is the force required to operate a door no greater than 5 lbs? (Fire doors may have up to 15 lbs to achieve positive latching). 11B-404.2.9, 11B-309.4			Yes ■ No ☐ N/A ☐
11.14	Door/Gate Closers	If the door/gate has a closer, is the closer adjusted so that from an open position of 90 degrees, the door/gate will take at least 5 seconds to move to a point 12" from the latch (measured to the leading edge of the door)? 11B-404.2.8.1	< 5 SEC		Yes ☐ No ■ N/A ☐
11.15	Spring Hinges	If the door/gate has spring hinges, is the closer adjusted so that from the open position of 70 degrees, the door/gate will close in 1.5 seconds minimum? 11B-404.2.8.2			Yes ☐ No ☐ N/A ■
11.16	Kick Plate	Does the bottom 10" of all doors except automatic and sliding have a smooth, uninterrupted surface on the push side to allow the door to be opened by a wheelchair footrest without creating a trap or hazardous condition? 11B-404.2.10			Yes ■ No ☐ N/A ☐
11.17	Powered Doors	If a power-assisted door is used, does it have an opening force of 5 lbs or less and does such door require no more than 15 lbs to stop door movement? 11B-404.3, ANSI A156.19			Yes ☐ No ☐ N/A ■
11.18	Auto Door Openers	If there are auto door openers, are there 2 push plates provided – CL of one 7" min and 8" max AFF and CL of second 30" min and 44" max AFF? Do both show ISA? 11B-404.2.9 Exception 2C			Yes ☐ No ☐ N/A ■
11.19	Room/Space Identification Signs	If there is a sign designating a permanent room or space, does it comply with the requirements below? 11B-216.2, 11B-703.4			Yes ☐ No ■ N/A ☐
11.20	Exit Door Signs (Visual/Tactile Signs)	At each grade level exterior exit door is there a tactile/Braille exit sign with the word "EXIT" mounted on the wall adjacent to the latch side of the door? 1011.4 item 1			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
11.21	Exit Door Signs (Visual/Tactile Signs)	At each exit door leading to a grade-level exterior exit by means of a stairway or ramp, is there a tactile/Braille exit sign with the words "EXIT STAIRS DOWN (or UP)" or "EXIT RAMP DOWN (or UP)" mounted on the wall adjacent to the latch side of the door? 1011.4 item 2			Yes ☐ No ☐ N/A ■
11.22	Exit Door Signs (Visual/Tactile Signs)	At each exit door that leads to a grade-level exterior exit by means of an exit enclosure that does not utilize a stair or ramp, or by means of an exit passageway, is there a tactile/Braille exit sign with the words "EXIT ROUTE" mounted on the wall adjacent to the latch side of the door? 1011.4 item 3			Yes ☐ No ☐ N/A ■
11.23	Exit Door Signs (Visual/Tactile Signs)	At each exit access door from an interior room or area that is required to have a visual exit sign, is there a tactile/Braille exit sign with the words "EXIT ROUTE" mounted on the wall adjacent to the latch side of the door? 1011.4 item 4	SIGN PROVIDED DOES NOT SAY "ROUTE"		Yes ☐ No ■ N/A ☐
11.24	Side of Doors	Are permanent identification signs located on the approach side of the door as one enters the room or space? Are exit signs located on the approach side of the door as one exits the room or space? 11B-703.4.2, 11B-216.2, 11B-216.4			Yes ■ No ☐ N/A ☐
11.25	Mounting Location (Visual/Tactile Signs)	Are tactile signs mounted on the wall adjacent to the latch side of the door at 48" min AFF? (measured from the baseline of the lowest Braille and 60" max AFF measured from the baseline of highest line of raised characters?) At double leaf doors with 1 active leaf, is the sign located on the inactive leaf? If there are 2 active leafs, is the sign located to the right of the right hand door? If there is no wall space at the latch side of a single door or at the right side of double doors, is the sign located on the nearest adjacent wall? 11B-703.4.1, 11B-703.4.2			Yes ■ No ☐ N/A ☐
11.26	Approach (Visual/Tactile Signs)	Is there a clear floor space of 18"min x 18"min, centered on the tactile characters, beyond the arc of any door swing? 11B-703.4.2			Yes ■ No ☐ N/A ☐
11.27	Tactile and Braille Characters (Visual/Tactile Signs	Are the characters on tactile signs accompanied by Grade 2 Braille? Is the Braille placed a min. of 3/8" and a max. of 1/2" below the tactile characters, flush left or centered, raised borders, and decorative elements? If the tactile text is multi-lined, is all Braille placed together below all lines of tactile text? Are the dots within each Braille cell 1/10" o.c., domed or rounded shape, and per Table 11B-703.3.1? 11B-703.3	BRAILLE IS NOT GRADE 2		Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

DOORS AND GATES

Survey Form 11

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
DOOR TO/FROM RECEPTION AREA & HALLWAY	IR2/ IR3		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
11.28	Character Size	Are the raised characters on tactile signs between 5/8" and 2" high, uppercase letter "O" 60% minimum and 110% maximum of the height of uppercase letter "I", stroke thickness of uppercase letter "I" shall be 15% maximum of the height of the character, and raised at least 1/32"? 11B-703.2.1, 11B-703.2.4, 11B-703.2.5, 11B-703.2.6			Yes ■ No ☐ N/A ☐
11.29	Upper Case	Are the raised characters on tactile signs upper case, and sans serif or simple serif? 11B-703.2.2, 11B-703.2.3			Yes ■ No ☐ N/A ☐
11.30	Contrast	Do the characters on signs contrast with their background (light-on-dark or dark-on-light) and do the signs have a non-glare finish? 11B-703.5.1			Yes ■ No ☐ N/A ☐
11.31	Other Identification Signage Requirements	Does the sign comply with all applicable requirements of Survey Form 19 - Signage? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this entrance. 4.30 /// 1117B.5			Yes ☐ No ■ N/A ☐
11.32	Vision Lights	If there is a glazing panel that permits viewing through the panel, is the bottom of at least one glazed panel located 43" maximum AFF? 11B-404.2.11	BOTTOM OF PANEL IS >43"		Yes ☐ No ■ N/A ☐
11.33	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ■ N/A ☐

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

- ALARM CONTROLS LOCATED ADJACENT TO DOOR HAVE OPERABLE PARTS LOCATED HIGHER THAN 48" ABOVE THE FINISHED FLOOR.

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

DEPARTMENT OF REHABILITATION – 4930 W KAWEAH COURT SUITE 100, VISALIA, CA 93277



FLOOR PLAN NTS

(IR2) DEPARTMENT OF REHABILITATION RECEPTION AREA





(IR2) DEPARTMENT OF REHABILITATION RECEPTION AREA

BUILDING LOBBIES AND CORRIDORS (Interior Accessible Route) — Survey Form 12A

Space/Room Item Name: DEPT. OF REHABILITATION HALLWAY	Item No.: 1R3	Floor No.:	Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
12.1A	Accessible Route	Is there an accessible route of travel connecting accessible entrances with all accessible elements and spaces within the building or facility, including mezzanines? 11B-206.2.4, 11B-402	SEE (1R2) DOOR SURVEY		Yes ☐ No ■ N/A ☐
12.2A	Width - General	Is the accessible route of travel, except at doorways, at least 44" wide where the occupancy load is ≥ 10, or at least 36" where the occupancy load is <10? 11B-403.5.1, 11N-403.5.3			Yes ■ No ☐ N/A ☐
12.3A	U-Turn	Where the accessible route of travel makes a U-turn around an obstacle which is less than 48" wide, is the accessible route at least 42" wide on the approaches and 48" wide in the turn? or Where the accessible route of travel makes a U-turn around an obstacle which is less than 60", is the accessible route at least 36" wide on the approaches and 60" wide in the turn? 11B-403.5.2, Fig. 11B-403.5.2			Yes ☐ No ☐ N/A ■
12.4A	Floor Surface	Are the floor surfaces on the accessible route of travel stable, firm, and slip-resistant? 11B-403.2, 11B-302			Yes ■ No ☐ N/A ☐
12.5A	Clear Door Opening	When the door is open 90 degrees, is there a clear opening width at least 32" measured between the face of the door and the doorstop on the latch side? Are projections into the clear opening width between 34" and 80" AFF not exceeding 4"? (Check the N/A box if doors are being documented by another portion of your survey.)11B-206.4, 11B-404.2.3			Yes ■ No ☐ N/A ☐
12.6A	Door Maneuvering Space	If the door is not automatic or power assisted, does it have maneuvering space relative to the direction of approach as shown in CBC Table11B-404.2.4.1?	HALLWAY "EXIT" DOOR - DOOR IS USED AS AN EMPLOYEE ENTRANCE/ EXIT - SEE PICTURES		Yes ☐ No ■ N/A ☐

Approach	*Side*	*Perpendicular to Door*	*Parallel to Door (beyond latch side unless noted)*
Front	Pull	60"	18"*****
Front	Push	48"	0"*
Hinge	Pull	60"	36"
Hinge	Push	44"**	22"***
Latch	Pull	60"****	24"
Latch	Push	44"****	24"

* Add 12" if closer and latch are provided.
** Add 4" if closer and latch are provided.
*** Beyond hinge side.
**** Add 4" if closer is provided.
***** Add 6" at exterior side of exterior doors.

11B-404.2.4, 11B-404.2.3

12.7A	Door Hardware	Are all handles, locks, and latches or other operative devices operable with one hand? 11B-309.4, 11B-404.2.7			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
12.8A	Door Operating Effort	Is the force required to operate a door no greater than 5 lbs? (Fire doors may have up to 15 lbs to achieve positive latching). 11B-404.2.9	16#'s @ HALLWAY FIRE DOOR		Yes ☐ No ■ N/A ☐
12.9A	Revolving Door	If a revolving door or turnstile is used on an accessible route, is an accessible door or gate provided adjacent to the revolving door or turnstile to facilitate the same use pattern? 11B-206.3, 11B-404.3.1			Yes ☐ No ☐ N/A ■
12.10A	Other Door Requirements	Does the door comply with all applicable requirements of Survey Form 11 - Doors and Gates? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this interior accessible route. 11B-206.4	11.6 11.25 11.11 11.27 11.13 11.14 11.23		Yes ☐ No ■ N/A ☐
12.11A	Directional and Informational Signs	Do signs which provide direction to, or information about, functional spaces of the building interior and exterior comply with the requirement for visual signage? EXCEPTION: Building directories, menus, and all other signs which are temporary are not required to comply. 11B-216.3, 11B.703.5			Yes ☐ No ■ N/A ☐
12.12A	Room/Space Identification Signs	Do signs which identify permanent rooms and spaces comply with the visual and tactile/Braille requirements below? (Check the N/A box if room identification signs are being documented by another portion of your survey.) 11B-216.2, 11B-703.1, 11B-703.2, 11B-703.3			Yes ☐ No ■ N/A ☐
12.13A	Tactile Exit Signs	At each grade level exterior exit door is there a tactile/Braille exit sign with the word "EXIT" mounted on the wall adjacent to the latch side of the door? 1011.4 item 1			Yes ☐ No ☐ N/A ■
12.14A	Tactile Exit Signs	At each exit door leading to a grade-level exterior exit by means of a stairway or ramp, is there a tactile/Braille exit sign with the words "EXIT STAIRS DOWN (or UP)" or "EXIT RAMP DOWN (or UP)" mounted on the wall adjacent to the latch side of the door? 1011.4 item 2			Yes ☐ No ☐ N/A ■
12.15A	Tactile Exit Signs	At each exit door that leads to a grade-level exterior exit by means of an exit enclosure that does not utilize a stair or ramp, or by means of an exit passageway, is there a tactile/Braille exit sign with the words "EXIT ROUTE" mounted on the wall adjacent to the latch side of the door? 1011.4 item 3			Yes ☐ No ☐ N/A ■
12.16A	Side of Doors	Are permanent identification signs located on the approach side of the door as one enters the room or space? Are exit signs located on the approach side of the door as one exits the room or space? 11B-216.2, 11B-216.4, 11B-703.4.2			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
12.17A	Mounting Location (Visual/Tactile Signs)	Are tactile signs mounted on the wall adjacent to the latch side of the door 48" min from baseline of lowest Braille to 60" max AFF from baseline of highest line of raised characters? For double doors with one active leaf, is the sign located on the inactive leaf? For double doors with both active leafs, is the sign located to the right of the right hand door? If there is no wall space, is the sign located at the latch side of a single door or at the right side of double door on the nearest adjacent wall? 11B-703.4.1 Figure 11B-703.4.1, 11B-703.4.2	ROOM SIGNS >60" TO BASELINES OF RAISED CHARACTERS		Yes ☐ No ■ N/A ☐
12.18A	Approach (Visual/Tactile Signs)	Is there a clear floor space of 18"min x 18"min, centered on the tactile characters, beyond the arc of any door swing between the closed position and 45 degree open position? 11B-703.4.2			Yes ■ No ☐ N/A ☐
12.19A	Tactile and Braille Characters	Are the characters on tactile signs accompanied by Grade 2 Braille? Are the Braille dots domed or rounded shape and is the Braille placed a min. of 3/8" and a max. of 1/2" below the tactile characters, flush left or centered and 3/8" minimum from raised borders and decorative elements? If the tactile text is multi-lined, is all Braille placed together below all lines of tactile text? Are the dots within each Braille cell 1/10" o.c.? 11B-703.3, 11B-703.3.1, 11B-703.3.2, Table 11B-703.3.1	ROOM SIGNS BRAILLE IS NOT GRADE 2		Yes ☐ No ■ N/A ☐
12.20A	Character Size	Are the raised characters on tactile signs between 5/8" and 2" high and raised at least 1/32"? 11B-703.2.1, 11B-703.2.5			Yes ■ No ☐ N/A ☐
12.21A	Upper Case	Are the raised characters on tactile signs upper case, and sans serif or simple serif? 11B-703.2.2, 11B-703.2.3			Yes ■ No ☐ N/A ☐
12.22A	Contrast	Do the characters on signs contrast with their background (light-on-dark or dark-on-light) and do the signs have a non-glare finish? 11B-703.5, 11B-703.6.2, 11B-703.7.1			Yes ■ No ☐ N/A ☐
12.23A	Other Identification Signage Requirements	Does the sign comply with all applicable requirements of Survey Form 19 - Signage? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this entrance. 11B-703	19.1 19.5 19.9 19.12 19.14		Yes ☐ No ■ N/A ☐
12.24A	Counter Height	At reception, transaction, or security counters, is there a portion of the main counter at least 36" long and 28" minimum and 34" maximum high? 11B-226.1, 11B-902.3			Yes ☐ No ☐ N/A ■
12.25A	Counter Knee Space	Where seated service at a counter is provided, is the knee space at least 27" high, 30" wide, and 19" deep? 11B-306.2.3 exception. 2, 11B-306.3.3 exception 2			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

BUILDING LOBBIES AND CORRIDORS (Interior Accessible Route) — Survey Form 12A

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
D.a R. HALLWAY	1R3		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
12.26A	Changes in Level	Are ramps or elevators used for changes in level greater than 1/2"? (Platform lifts may only be used in certain limited situations.) 11B-303.4			Yes ☐ No ☐ N/A ■
12.27A	Protruding Objects	If objects mounted to the wall have leading edges between 27 and 80" from the floor, do they project less than 4" into the circulation path? (Wall mounted objects with leading edges at or below 27" may project any amount so long as the required clear width of an accessible route is not reduced.) If a guardrail or barrier is provided, is it maximum 27"AFF? 11B-307.2, 11B-307.3, 11B-307.4			Yes ☐ No ☐ N/A ■
12.28A	Head room	Is there at least 80" clear head room within the pedestrian circulation area, including the accessible route of travel? 11B-307.4			Yes ■ No ☐ N/A ☐
12.29A	Alarms	If emergency warning systems are provided, do they include both audible alarms and visual alarms complying with Survey Form 20 - Alarms? 907.5.2.1 (Audible), 907.5.2.3 (Visible), 11B-215			Yes ☐ No ☐ N/A ■
12.30A	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ■ N/A ☐

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

- THE OPERABLE PARTS OF FIRE EXTINGUISHERS WITHIN THE SUITE 100 HALLWAY ARE LOCATED HIGHER THAN 48" ABOVE THE FINISHED FLOOR.

- ALARM CONTROL PANELS LOCATED WITHIN THE HALLWAYS HAVE THE OPERABLE PARTS LOCATED HIGHER THAN 48" ABOVE THE FINISHED FLOOR.

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

DEPARTMENT OF REHABILITATION – 4930 W KAWEAH COURT SUITE 100, VISALIA, CA 93277



FLOOR PLAN NTS



(IR3) DEPARTMENT OF REHABILITATION HALLWAYS





(IR3) DEPARTMENT OF REHABILITATION HALLWAYS







(IR3) DEPARTMENT OF REHABILITATION HALLWAYS





(IR3) DEPARTMENT OF REHABILITATION HALLWAYS

(IR3) DEPARTMENT OF REHABILITATION HALLWAYS





(IR3) DEPARTMENT OF REHABILITATION HALLWAYS







(IR3) DEPARTMENT OF REHABILITATION HALLWAYS

(IR3) DEPARTMENT OF REHABILITATION HALLWAYS

Facility
Name: DEPARTMENT OF REHABILITATION

RESD
Project No.: 139602

In facilities with a small number of the same type of rooms or spaces where rooms or spaces typically do not have similar or the same barriers, document all findings on Summary Sheet F1 - Rooms and Spaces (Small Number) and on Survey Form 14 - Rooms and Spaces.

How to use this form: In the table below list the names or numbers of rooms and spaces where violations of Survey Form 14 (SF14) were found. Insert the room ID adjacent to the corresponding Item Number, using SF14 as a reference. Add any pertinent as-built measurements or survey comments on a separate sheet. Use the unnumbered cells at the bottom of the table to enter item numbers (Item No.) from survey forms other than SF14 and the room ID of the rooms and spaces where these barriers were detected. In the last line of the table (None) list the names or numbers of all rooms and spaces where no violation of Survey Form 14 or any other Survey Form was found.

Rooms and Spaces (Large Number)
Note: For scoping and exceptions see Summary Sheet F1

Item No.	Room ID (names or numbers)	Item No.	Room ID (names or numbers)	Item No.	Room ID (names or numbers)
14.2		**14.3**		**14.4**	102,103,104,105,108,112,113, 114,116,117,118,119
14.5		**14.6**		**14.7**	
14.8	102,103,104,105,106,107,108, 110,111,112,113,114,115,116, 117,118,119	**14.9**		**14.10**	
14.11		**14.12**	106,108	**14.13**	113
14.14	102,103,104,105,106,107,108, 110,111,112,113,114,115,116, 117,118,119	**14.15**		**14.16**	102,103,104,105,106,107,108, 110,111,112,113,114,115,116, 117,118,119
14.17		**14.18**		**14.19**	
14.20		**14.21**		**14.22**	
14.23		**14.24**		**14.25**	
14.26		**14.27**		**14.28**	
14.29		**14.30**		**14.31**	
14.32		**14.33**		**14.34**	
14.35	106	**14.37**	101-119 (OUTLETS)	**14.40**	105
14.41	105	**14.42**	105 (INSTAHOT)		
None					



FLOOR PLAN NTS



ROOMS AND SPACES





ROOMS AND SPACES

ROOMS AND SPACES









ROOMS AND SPACES







ROOMS AND SPACES

Facility
Name: DEPARTMENT OF REHABILITATION

RESD
Project No.: 139602

Toilet Rooms

Each public and common use toilet room must be accessible and comply with CBC 11B213, 11B-603, 11B-604. Employee toilet rooms are considered to be "common use" toilet rooms.

In outdoor use areas, where single user portable toilet units are provided at a single location, at least 5% (but not less than one) accessible toilet units must be installed at each cluster whenever typical inaccessible units are provided. The International Symbol of Accessibility (ISA) must identify accessible units.

List all toilet rooms in the following table and survey each of these areas with a separate copy of Survey Form 16 - Toilet Rooms. If you encounter doors, gates, alarms, or drinking fountains, survey that element with its specific survey form:

ID	Name/location/function of toilet room (or key number on site plan)	If not fully accessible, indicate distance to next accessible toilet room of same type.	Room No.	On floor
TR1	MEN'S RESTROOM	N/A		1
TR2	WOMEN'S RESTROOM	N/A		1
TR3				
TR4				
TR5				
TR6				

*Indicate the number of Survey Forms attached to Summary Sheet G in the **No**. field.*

Form	Item	No.		Form	Item	No.		Form	Item	No.
SF5	Drinking Fountains			SF11	Doors and Gates			SF16	Toilet Rooms	2
SF20	Alarms			SF ..				SF ..		

TOILET FACILITIES

Survey Form 16

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
MEN'S RESTROOM	TR1		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.1	Toilet Rooms	If toilet rooms are provided, does each public and common use toilet room comply with the requirements below? (A common use toilet room is used for a restricted group of people such as occupants of a building or employees of a company.) 11B-213.2, 11B-603.2			Yes ☐ No ■ N/A ☐
16.2	Gender Separate Toilet Rooms	Where separate facilities are provided for persons of each sex, are these facilities accessible? 11B-213.2			Yes ☐ No ■ N/A ☐
16.3	Unisex Toilet Rooms	Where unisex facilities are provided are these facilities accessible? 11B-213.2			Yes ☐ No ☐ N/A ■
16.4	Accessible Route of Travel	Is the toilet room located on an accessible route of travel? 4.11B-202.4			Yes ■ No ☐ N/A ☐
16.5	Fixtures	If provided, are each of the following accessible fixtures and controls located on an accessible route within the toilet room? - Water closet (WC) - Lavatory - Urinal - Controls, Dispensers, and Mirrors 11B-213, 11B-603.2	ROUTE W/IN THE RESTROOM IS ACCESSIBLE FIXTURES ARE NOT ACCESSIBLE		Yes ■ No ☐ N/A ☐
16.6	Entry Doors	Does the door comply with the requirements below? 11B-603.2.3, 11B-604.8.1.2			Yes ☐ No ■ N/A ☐
16.7	Clear Door Opening	When the door is open 90 degrees, is there a clear opening width at least 32" measured between the face of the door and the doorstop on the latch side? 11B-404.2.3			Yes ■ No ☐ N/A ☐
16.8	Door Swing	Does the door swing not intrude into the clear floor space at any fixture? Other than the door to the accessible water closet compartment, a door in any position, may encroach into the turning space by 12" maximum. 11B-603.2.3			Yes ■ No ☐ N/A ☐
16.9	Door Hardware	Are all handles, locks, and latches or other operative devices operable with one hand? 11B-404.2.7, 11B-309.4			Yes ■ No ☐ N/A ☐
16.10	Door Operating Effort	Is the force required to operate a door no greater than 5 lbs? (Fire doors may have up to 15 lbs to achieve positive latching). 11B-404.2.9	10 #'s		Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.11	Door Maneuvering Space	If the door is not automatic or power assisted, does it have maneuvering space relative to the direction of approach as shown in CBC Table11B-404.2.4.1 *Approach* / *Side* / *Perpendicular to Door* / *Parallel to Door (beyond latch side unless noted)* Front / Pull / 60" / 18"***** Front / Push / 48" / 0"** Hinge / Pull / 60" / 36" Hinge / Push / 44"*** / 22"**** Latch / Pull / 60"***** / 24" Latch / Push / 44"***** / 24" * Add 12" if closer and latch are provided. ** Add 4" if closer and latch are provided. *** Beyond hinge side. **** Add 4" if closer is provided. ***** Add 6" at exterior side of exterior doors. 11B-404.2.4, 11B-404.2.4.3			Yes ☐ No ■ N/A ☐
16.12	Other Door Requirements	Does the door comply with all applicable requirements of Survey Form 11 - Doors and Gates? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this interior accessible route. 11B-206.5, 11B-404.1	11.6 11.13 11.19 11.26 11.27		Yes ☐ No ■ N/A ☐
16.13	Identification Symbols	Is each doorway leading to a men's toilet room identified by an equilateral triangle 1/4" thick with edges 12" long, and is each women's toilet room identified by a circle, 1/4" thick and 12" in diameter? (Unisex facilities shall be identified by a 12" circle, 1/4" with a 1/4" thick triangle superimposed and within the circle.) 11B-216.8, 11B-703.7.2.6			Yes ■ No ☐ N/A ☐
16.14	Identification Symbols	Is the geometric symbol centered on the door leaf at a height of 58" minimum and 60" maximum AFF and is the symbol's color and contrast distinctly different from the color and contrast of the door? 11B-703.7.2.6			Yes ■ No ☐ N/A ☐
16.15	Room/Space Identification Signs	In addition, is there a tactile room identification sign complying with the requirements below? 11B-216.2, 11B-703.2, 11B-703.6	BRAILLE IS NOT GRADE 2		Yes ☐ No ■ N/A ☐
16.16	Gender	Is the gender indicated on the sign by raised letters (men's, women's, boys', girls')? 11B-703.2, 11B-703.6.3			Yes ■ No ☐ N/A ☐
16.17	Pictogram	Is there a gender pictogram provided directly above the raised letters 11B-703.6.1, 11B-703.6.3			Yes ■ No ☐ N/A ☐
16.18	ISA	If the toilet room is accessible, is the room identified by an ISA? 11B-703.7			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.19	Mounting Location (Visual/Tactile Signs)	Are tactile signs mounted on the wall adjacent to the latch side of the door at 48" minimum AFF measured from the baseline of the lowest Braille and 60" maximum AFF measured from the baseline of the highest line of raised characters? (If there is no wall space at the latch side of a single door or at the right side of double doors, is the sign located on the nearest adjacent wall?) 11B-703.4.1, 11B-703.4.2			Yes ■ No ☐ N/A ☐
16.20	Approach (Visual/Tactile Signs)	Is there a clear floor space of 18"min x 18"min centered on the tactile characters, beyond the arc of any door swing? 11B-703.4.2	±15"		Yes ☐ No ■ N/A ☐
16.21	Tactile and Braille Characters (Visual/Tactile Signs)	Are the characters on tactile signs accompanied by Grade 2 Braille? Is the Braille placed a min. of 3/8" and a max. of 1/2" below the tactile characters, flush left or centered? If the tactile text is multi-lined, is all Braille placed together below all lines of tactile text? Are the dots within each Braille cell 1/10" o.c., domed or rounded shape, and per Table 11B-703.3.1? 11B-703.3	BRAILLE IS NOT GRADE 2		Yes ☐ No ■ N/A ☐
16.22	Character Size (Visual/Tactile Signs)	Are the raised characters on tactile signs between 5/8" and 2" high, uppercase letter "O" 60% minimum and 110% maximum of the height of uppercase letter "I", stroke thickness of uppercase letter "I shall be 15% maximum of the height of the character and raised at least 1/32"? 11B-703.2.1, 11B-703.2.4, 11B-703.2.5, 11B-703.2.6			Yes ■ No ☐ N/A ☐
16.23	Upper Case	Are the raised characters on tactile signs upper case, and sans serif or simple serif? 11B-703.2.2, 11B-703.2.3			Yes ■ No ☐ N/A ☐
16.24	Contrast	Do the characters on signs contrast with their background (light-on-dark or dark-on-light) and do the signs have a non-glare finish? 11B-703.5.1, 11B-703.6.2, 11B-703.7.1			Yes ■ No ☐ N/A ☐
16.25	Other Identification Signage Requirements	Does the sign comply with all applicable requirements of Survey Form 19 - Signage? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this entrance. 11B-703	19.13 19.14		Yes ☐ No ■ N/A ☐
16.26	Floor Surface	Is the surface of the toilet room stable, firm, and slip resistant? 11B-302, 11B-302.1			Yes ■ No ☐ N/A ☐
16.27	Maneuvering Space	Is there an unobstructed turning space (a 60" diameter circle or T-shaped space) in the toilet room? (The clear floor space of fixtures and controls, the accessible route of travel, and the turning space may overlap.). 11B-603.2, 11B-304			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Space/Room Item Name: MEN'S RESTROOM | Item No.: TR1 | Floor No.: | Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.28	Maneuvering Space	Other than the door to the accessible WC compartment, no door, in any position, encroaches into this turning space for more than 12". 11B-603.2, 11B-304			Yes ■ No □ N/A □
16.29	Maneuvering Space	Is the waste bin located where it does not protrude into any required accessible route of travel, turning space, door swing, or any clear floor space of fixtures or dispensers? 11B-603.2, 11B-304	PROTRUDES INTO DOOR MANEUVERING SPACE		Yes □ No ■ N/A □
16.30	Stall Door Width	In front entry stalls: When the stall door is open 90 degrees, is there a clear opening of at least 32" measured between the face of the door and the edge of the partition on the latch side? 11B-604.8.1.2, 11B-404			Yes ■ No □ N/A □
16.31	Stall Door Width	In side entry stalls: When the stall door is open 90 degrees, is there a clear opening of at least 34" measured between the face of the door and the edge of the partition on the latch side? 11B-604.8.1.2 Exception			Yes □ No □ N/A ■
16.32	Stall Door Hardware	Does the stall door have U-pulls on both sides and a locking mechanism operable with one hand without tight grasping, pinching, or twisting of the wrist? 11B-604.8.1.2, 11B-404.2.7			Yes ■ No □ N/A □
16.33	Stall Door	Is the stall door self-closing? 11B-604.8.1.2			Yes □ No ■ N/A □
16.34	Approach Aisle to Stall	If the stall door swings out, is the aisle approaching the stall at least 60" wide? 4.17.5 /// 1115B.3.1 item 4.3			Yes ■ No □ N/A □
16.35	Stall Width	Is the stall at least 60" wide? 11B-604.8.1.1, Fig 11B-604.8.1.1.2, 11B-604.8.1.1.3			Yes ■ No □ N/A □
16.36	Stall Maneuvering Space	If the stall has a side entry stall door, is there a 60" by 60" clear floor space in front of the WC? 11B-604.8.1.1.1, 11B-604.8.1.1.2			Yes □ No □ N/A ■
16.37	Stall Maneuvering Space	If the stall has an in-swinging side entry stall door, is there a 60" min wide by 56" min deep space for a wall-mounted WC, or a 60" min wide by 59" min deep space for floor-mounted WC? Figure 11B-604.8.1.1			Yes □ No □ N/A ■
16.38	Stall Maneuvering Space	If the stall has an end entry stall door, is there at least a 60" wide by 48" deep clear floor space in front of the WC? 11B-604.8.1.1.3, Figure 11B-604.8.1.1.3			Yes ■ No □ N/A □
16.39	Stall Door Location	If the stall has an end entry stall door, is the stall door located in front of the clear floor space - diagonal to the WC - with a maximum stile width of 4 inches? 11B-604.8.1.2, Fig. 11B-604.8.1.2			Yes □ No ■ N/A □

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

TOILET FACILITIES

Survey Form 16

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
MEN'S RESTROOM	TR1		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.40	Clear Floor Space at fixtures	Is there a clear floor or ground space of 30" x 48" minimum beyond the arc of the door swing?(Other than the door to the accessible water closet compartment, a door, in any position, may encroach into the turning space by 12" maximum). 11B-603.2.1, 11B-603.2.3, 11B-305.3			Yes ■ No ☐ N/A ☐
16.41	Clear Floor Space – Individual use	Is there a clear floor or ground space 30" x 48" minimum beyond the arc of the door? (Doors may swing into the clear floor space or clearance required for any fixture). 11B-603.2.3 Exception 2, 11B-305.3			Yes ☐ No ☐ N/A ■
16.42	WC Location	Is the centerline of the WC 17" minimum to 18" maximum (17" minimum to 19" maximum for ambulatory accessible WC) from a wall or partition? 11B-604.2	± 18¼"-18½"		Yes ☐ No ■ N/A ☐
16.43	WC Seat	Is the top of the WC seat between 17" and 19" AFF? 11B-604.4			Yes ■ No ☐ N/A ☐
16.44	WC Flush Controls	Are flush controls automatic or operable with one hand and located on the wide side of the WC where the clear floor space is provided and 44" maximum AFF? 11B-604.6, 11B-309			Yes ■ No ☐ N/A ☐
16.45	Toilet Paper Dispenser	Is the toilet paper between 7" minimum and 9" maximum in front of the WC measured to the centerline of the dispenser and centered at least 19" minimum AFF below the grab bar? 11B-604.7, 11B-309.4, Fig 11B-604.7			Yes ■ No ☐ N/A ☐
16.46	Toilet Paper Dispenser	Is the toilet paper dispenser mounted below the side grab bar? 11B-607.7, Figure 11B-604.7			Yes ■ No ☐ N/A ☐
16.47	Toilet Paper Dispenser	Does the toilet paper dispenser allow continuous paper delivery? 11B-604.7			Yes ■ No ☐ N/A ☐
16.48	Seat Cover Dispenser	Is the highest operable part of the seat cover dispenser no higher than 40 inches AFF? 11B-603.5	± 42"		Yes ☐ No ■ N/A ☐
16.49	Grab Bars	Is there a 42" side grab bar (24" minimum in front of the WC)and a 36" rear grab bar (12" minimum from CL of toilet to wall side) in the stall, 33 minimum and 36" maximum AFF measured to the top of the gripping surface? 11B-604.5.1, 11B-604.5.2, Figures 11B-604.5.1, 11B-604.5.2, 11B-604.8.1.5, 11B-609.4	SIDE ok REAR Ø		Yes ☐ No ■ N/A ☐
16.50	Grab Bar Diameter	Is the outside diameter of the grab bar between 1-1/4" and 2" and 2" maximum for non-circular? 11B-609.2.1, 609.2.2			Yes ■ No ☐ N/A ☐
16.51	Grab Bar Wall Clearance	Is the space between the grab bar and the wall exactly 1-1/2 inches? 11B-609.3			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

TOILET FACILITIES

Survey Form 16

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
MEN'S RESTROOM	TR1		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.52	Grab Bar Clearance	Is any dispenser located so that it does not obstruct the use of the grab bar (e.g., no closer than 12" above and1-1/2" below the tangent point of the grab bar unless dispenser is recess, flush with wall and has no sharp edges)? 11B-609.3	RECESSED		Yes ■ No ☐ N/A ☐
16.53	Hazards at Grab Bars	Are grab bars and adjacent walls free of sharp or abrasive elements? 11B-609.5			Yes ■ No ☐ N/A ☐
16.54	Side Grab Bar	Does the side grab bar extend at least 54" min beyond the rear wall while the other end is a maximum of 12" from the rear wall, with the front end positioned 24" min. in front of the WC? 11B-604.5.1, Figure 11B-604.5.1			Yes ■ No ☐ N/A ☐
16.55	Rear Grab Bar	Does the rear grab bar extend from the centerline of the WC 12" min. on one side and 24" min. on the other side? 11B-604.5.2, Figure 11B-604.5.2			Yes ☐ No ■ N/A ☐
16.56	Semi-Ambulant Stall	Where 6 or more toilet stalls (or combination of urinals and water closets) are provided, in addition to the 60" wide accessible stall, is at least one semi-ambulant stall 35"-37"wide with an outward swinging, self-closing door provided? 11B-213.3.1, 11B-604.8.2			Yes ☐ No ☐ N/A ■
16.57	Semi-Ambulant Stall	Are there two side grab bars in the semi-ambulant stall, 42" in length, and located 12" maximum from the rear wall? 11B-604.8.2.3, 11B-604.5.1			Yes ☐ No ☐ N/A ■
16.58	Urinals	Where urinals are provided, does at least one comply with the requirements below? 11B-605			Yes ☐ No ■ N/A ☐
16.59	Urinal Rim Height	Does the urinal have an elongated rim projecting at least 13 1/2" from the wall and a maximum of 17" AFF? 11B-605.2, Figure 11-B-605.2			Yes ■ No ☐ N/A ☐
16.60	Clear Floor Space at Urinal	Is there a clear floor space at least 30" x 48" which allows a forward approach to the urinal? 11B-605.3, 11B-305			Yes ■ No ☐ N/A ☐
16.61	Width Between Screens at Urinal	If urinal screens are provided and they extend 24" or less, is there at least 30" between the two panels? 11B-305.5	SCREENS >24"		Yes ☐ No ☐ N/A ■
16.62	Width Between Screens at Urinal	If urinal screens are provided and they extend more than 24", is there at least 36" between the two panels? 11B-305.7.1	32 1/4"		Yes ☐ No ■ N/A ☐
16.63	Lavatories	If lavatories are provided, does at least one lavatory meet the requirements below? 11B-213.3.4, 11B-606			Yes ☐ No ■ N/A ☐
16.64	Lavatory Rim Height	Is the lavatory rim or counter surface no higher than 34" AFF? 11B-606.3	±34 1/2" TO RIM		Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.65	Clear Floor space at Lavatory	Is there a clear floor space at least 30" x 48" in front of the lavatory allowing a forward approach? 11B-606.2, 11B-305			Yes ■ No ☐ N/A ☐
16.66	Lavatory Knee Clearance	Is there space below the lavatory 27"high minimum AFF at a depth of 8" minimum increasing to 29" high minimum at the front edge of the counter or the front edge of the wall-mounted lavatory? Between 9" and 27" AFF, the knee clearance can be reduced at a rate of 1" in depth for each 6" in height. 11B-306.3.3 exception 1, 11B-306.3.4, Figure 11B-306.3	28" @ FRONT EDGE OF COUNTER		Yes ☐ No ■ N/A ☐
16.67	Lavatory Toe Clearance	Does the toe clearance extend 19" minimum and 25" maximum and is it 30" wide minimum? 11B-306.2			Yes ■ No ☐ N/A ☐
16.68	Lavatory Wall Projection	Does the front edge of the lavatory project a maximum of 25" at 9" AFF? 11B-306.3.2			Yes ■ No ☐ N/A ☐
16.69	Side Clearance at Lavatory	Is there a minimum of 18" from the centerline of the lavatory to the nearest sidewall or partition? 11B-606.6			Yes ■ No ☐ N/A ☐
16.70	Pipe Insulation at Lavatory	Are water supply and drainpipes insulated to protect against contact? 11B-606.5			Yes ☐ No ■ N/A ☐
16.71	Smooth Surfaces at Lavatory	Is the area below the lavatory free of sharp or abrasive surfaces? 11B-606.5	HOSE BIBB		Yes ☐ No ■ N/A ☐
16.72	Faucet Operation at Lavatory	Can the faucet be operated with one hand without tight grasping, pinching, or twisting of the wrist with 5 lbs. maximum to activate operable parts? 11B-606.4, 11B-309			Yes ■ No ☐ N/A ☐
16.73	Faucet Operation at Lavatory	If the valve is self-closing, does it remain open for at least 10 seconds? 11B-606.4			Yes ☐ No ☐ N/A ■
16.74	Mirrors	Where mirrors are provided, does at least one mirror have the bottom edge of the reflecting surface no higher than 40" AFF if located above sink or countertop? If not above sink or countertop, is the bottom edge of the reflecting surface no higher than 35" AFF? 11B-203.3.5, 11B-603.3			Yes ■ No ☐ N/A ☐
16.75	Coat Hook	Where a coat hook is provided in an accessible stall is it 48" maximum AFF? 11B-213.3.7, 11B-604.8.3, 11B-308			Yes ■ No ☐ N/A ☐
16.76	Dispensers Operating Height	Is at least one of each dispenser type accessible and is the highest operable part no higher than 40" AFF? (Indicate type, e.g., paper towel dispenser [PTD], electrical dryer [ED], soap dispenser [SD], and height in inches.) 11B-603.5			Yes ■ No ☐ N/A ☐
16.77	Floor Space at Dispensers	Is there a clear floor space at least 30" x 48" in front of the dispenser allowing either a forward or a parallel approach to the dispenser? 11B-309.2, 11B-305			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Space/Room Item Name: MEN'S RESTROOM | Item No.: TR1 | Floor No.: | Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.78	Dispenser Operation	Can the dispenser be operated with one hand without tight grasping, pinching, or twisting of the wrist? 11B-309.4			Yes ■ No ☐ N/A ☐
16.79	Alarm	In buildings where an emergency warning system is required, is there a visual alarm (strobe) in the toilet room? 907.5.2.3, 11B-215			Yes ☐ No ☐ N/A ■
16.80	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

- ✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities



RESTROOMS NTS

(TR1) MEN'S RESTROOM

(TR1) MEN'S RESTROOM

(TR1) MEN'S RESTROOM



(TR1) MEN'S RESTROOM

TOILET FACILITIES

Survey Form 16

Space/Room Item Name:	Item No.:	Floor No.:	Project No.:
WOMEN'S RESTROOM	TR2		139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.1	Toilet Rooms	If toilet rooms are provided, does each public and common use toilet room comply with the requirements below? (A common use toilet room is used for a restricted group of people such as occupants of a building or employees of a company.) 11B-213.2, 11B-603.2			Yes ☐ No ■ N/A ☐
16.2	Gender Separate Toilet Rooms	Where separate facilities are provided for persons of each sex, are these facilities accessible? 11B-213.2			Yes ☐ No ■ N/A ☐
16.3	Unisex Toilet Rooms	Where unisex facilities are provided are these facilities accessible? 11B-213.2			Yes ☐ No ☐ N/A ■
16.4	Accessible Route of Travel	Is the toilet room located on an accessible route of travel? 4.11B-202.4			Yes ■ No ☐ N/A ☐
16.5	Fixtures	If provided, are each of the following accessible fixtures and controls located on an accessible route within the toilet room? - Water closet (WC) - Lavatory - Urinal - Controls, Dispensers, and Mirrors 11B-213, 11B-603.2	ROUTE W/IN THE RESTROOM IS ACCESSIBLE FIXTURES ARE NOT ACCESSIBLE		Yes ■ No ☐ N/A ☐
16.6	Entry Doors	Does the door comply with the requirements below? 11B-603.2.3, 11B-604.8.1.2			Yes ☐ No ■ N/A ☐
16.7	Clear Door Opening	When the door is open 90 degrees, is there a clear opening width at least 32" measured between the face of the door and the doorstop on the latch side? 11B-404.2.3			Yes ■ No ☐ N/A ☐
16.8	Door Swing	Does the door swing not intrude into the clear floor space at any fixture? Other than the door to the accessible water closet compartment, a door in any position, may encroach into the turning space by 12" maximum. 11B-603.2.3			Yes ■ No ☐ N/A ☐
16.9	Door Hardware	Are all handles, locks, and latches or other operative devices operable with one hand? 11B-404.2.7, 11B-309.4			Yes ■ No ☐ N/A ☐
16.10	Door Operating Effort	Is the force required to operate a door no greater than 5 lbs? (Fire doors may have up to 15 lbs to achieve positive latching). 11B-404.2.9	10#'s		Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.11	Door Maneuvering Space	If the door is not automatic or power assisted, does it have maneuvering space relative to the direction of approach as shown in CBC Table11B-404.2.4.1 *Approach* / *Side* / *Perpendicular to Door* / *Parallel to Door (beyond latch side unless noted)* Front / Pull / 60" / 18"***** Front / Push / 48" / 0"* Hinge / Pull / 60" / 36" Hinge / Push / 44"** / 22"*** Latch / Pull / 60"**** / 24" Latch / Push / 44"**** / 24" * Add 12" if closer and latch are provided. ** Add 4" if closer and latch are provided. *** Beyond hinge side. **** Add 4" if closer is provided. ***** Add 6" at exterior side of exterior doors. 11B-404.2.4, 11B-404.2.4.3			Yes ☐ No ■ N/A ☐
16.12	Other Door Requirements	Does the door comply with all applicable requirements of Survey Form 11 - Doors and Gates? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this interior accessible route. 11B-206.5, 11B-404.1	11.6 11.13 11.19 11.26 11.27		Yes ☐ No ■ N/A ☐
16.13	Identification Symbols	Is each doorway leading to a men's toilet room identified by an equilateral triangle 1/4" thick with edges 12" long, and is each women's toilet room identified by a circle, 1/4" thick and 12" in diameter? (Unisex facilities shall be identified by a 12" circle, 1/4" with a 1/4" thick triangle superimposed and within the circle.) 11B-216.8, 11B-703.7.2.6			Yes ■ No ☐ N/A ☐
16.14	Identification Symbols	Is the geometric symbol centered on the door leaf at a height of 58" minimum and 60" maximum AFF and is the symbol's color and contrast distinctly different from the color and contrast of the door? 11B-703.7.2.6	± 60 1/2"		Yes ☐ No ■ N/A ☐
16.15	Room/Space Identification Signs	In addition, is there a tactile room identification sign complying with the requirements below? 11B-216.2, 11B-703.2, 11B-703.6	BRAILLE IS NOT GRADE 2		Yes ☐ No ■ N/A ☐
16.16	Gender	Is the gender indicated on the sign by raised letters (men's, women's, boys', girls')? 11B-703.2, 11B-703.6.3			Yes ■ No ☐ N/A ☐
16.17	Pictogram	Is there a gender pictogram provided directly above the raised letters 11B-703.6.1, 11B-703.6.3			Yes ■ No ☐ N/A ☐
16.18	ISA	If the toilet room is accessible, is the room identified by an ISA? 11B-703.7			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.19	Mounting Location (Visual/Tactile Signs)	Are tactile signs mounted on the wall adjacent to the latch side of the door at 48" minimum AFF measured from the baseline of the lowest Braille and 60" maximum AFF measured from the baseline of the highest line of raised characters? (If there is no wall space at the latch side of a single door or at the right side of double doors, is the sign located on the nearest adjacent wall?) 11B-703.4.1, 11B-703.4.2			Yes ■ No ☐ N/A ☐
16.20	Approach (Visual/Tactile Signs)	Is there a clear floor space of 18"min x 18"min centered on the tactile characters, beyond the arc of any door swing? 11B-703.4.2	± 15"		Yes ☐ No ■ N/A ☐
16.21	Tactile and Braille Characters (Visual/Tactile Signs)	Are the characters on tactile signs accompanied by Grade 2 Braille? Is the Braille placed a min. of 3/8" and a max. of 1/2" below the tactile characters, flush left or centered? If the tactile text is multi-lined, is all Braille placed together below all lines of tactile text? Are the dots within each Braille cell 1/10" o.c., domed or rounded shape, and per Table 11B-703.3.1? 11B-703.3	BRAILLE IS NOT GRADE 2		Yes ☐ No ■ N/A ☐
16.22	Character Size (Visual/Tactile Signs)	Are the raised characters on tactile signs between 5/8" and 2" high, uppercase letter "O" 60% minimum and 110% maximum of the height of uppercase letter "I", stroke thickness of uppercase letter "I shall be 15% maximum of the height of the character and raised at least 1/32"? 11B-703.2.1, 11B-703.2.4, 11B-703.2.5, 11B-703.2.6			Yes ■ No ☐ N/A ☐
16.23	Upper Case	Are the raised characters on tactile signs upper case, and sans serif or simple serif? 11B-703.2.2, 11B-703.2.3			Yes ■ No ☐ N/A ☐
16.24	Contrast	Do the characters on signs contrast with their background (light-on-dark or dark-on-light) and do the signs have a non-glare finish? 11B-703.5.1, 11B-703.6.2, 11B-703.7.1			Yes ■ No ☐ N/A ☐
16.25	Other Identification Signage Requirements	Does the sign comply with all applicable requirements of Survey Form 19 - Signage? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this entrance. 11B-703	19.13 19.14		Yes ☐ No ■ N/A ☐
16.26	Floor Surface	Is the surface of the toilet room stable, firm, and slip resistant? 11B-302, 11B-302.1			Yes ■ No ☐ N/A ☐
16.27	Maneuvering Space	Is there an unobstructed turning space (a 60" diameter circle or T-shaped space) in the toilet room? (The clear floor space of fixtures and controls, the accessible route of travel, and the turning space may overlap.). 11B-603.2, 11B-304			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.28	Maneuvering Space	Other than the door to the accessible WC compartment, no door, in any position, encroaches into this turning space for more than 12". 11B-603.2, 11B-304			Yes ■ No ☐ N/A ☐
16.29	Maneuvering Space	Is the waste bin located where it does not protrude into any required accessible route of travel, turning space, door swing, or any clear floor space of fixtures or dispensers? 11B-603.2, 11B-304			Yes ■ No ☐ N/A ☐
16.30	Stall Door Width	In front entry stalls: When the stall door is open 90 degrees, is there a clear opening of at least 32" measured between the face of the door and the edge of the partition on the latch side? 11B-604.8.1.2, 11B-404			Yes ■ No ☐ N/A ☐
16.31	Stall Door Width	In side entry stalls: When the stall door is open 90 degrees, is there a clear opening of at least 34" measured between the face of the door and the edge of the partition on the latch side? 11B-604.8.1.2 Exception			Yes ☐ No ☐ N/A ■
16.32	Stall Door Hardware	Does the stall door have U-pulls on both sides and a locking mechanism operable with one hand without tight grasping, pinching, or twisting of the wrist? 11B-604.8.1.2, 11B-404.2.7			Yes ☐ No ■ N/A ☐
16.33	Stall Door	Is the stall door self-closing? 11B-604.8.1.2			Yes ☐ No ■ N/A ☐
16.34	Approach Aisle to Stall	If the stall door swings out, is the aisle approaching the stall at least 60" wide? 4.17.5 /// 1115B.3.1 item 4.3			Yes ☐ No ☐ N/A ■
16.35	Stall Width	Is the stall at least 60" wide? 11B-604.8.1.1, Fig 11B-604.8.1.1.2, 11B-604.8.1.1.3	59 1/2"		Yes ☐ No ■ N/A ☐
16.36	Stall Maneuvering Space	If the stall has a side entry stall door, is there a 60" by 60" clear floor space in front of the WC? 11B-604.8.1.1.1, 11B-604.8.1.1.2			Yes ☐ No ☐ N/A ■
16.37	Stall Maneuvering Space	If the stall has an in-swinging side entry stall door, is there a 60" min wide by 56" min deep space for a wall-mounted WC, or a 60" min wide by 59" min deep space for floor-mounted WC? Figure 11B-604.8.1.1			Yes ☐ No ☐ N/A ■
16.38	Stall Maneuvering Space	If the stall has an end entry stall door, is there at least a 60" wide by 48" deep clear floor space in front of the WC? 11B-604.8.1.1.3, Figure 11B-604.8.1.1.3	STALL NOT 60" WIDE		Yes ☐ No ■ N/A ☐
16.39	Stall Door Location	If the stall has an end entry stall door, is the stall door located in front of the clear floor space - diagonal to the WC - with a maximum stile width of 4 inches? 11B-604.8.1.2, Fig. 11B-604.8.1.2			Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.40	Clear Floor Space at fixtures	Is there a clear floor or ground space of 30" x 48" minimum beyond the arc of the door swing?(Other than the door to the accessible water closet compartment, a door, in any position, may encroach into the turning space by 12" maximum). 11B-603.2.1, 11B-603.2.3, 11B-305.3			Yes ■ No ☐ N/A ☐
16.41	Clear Floor Space – Individual use	Is there a clear floor or ground space 30" x 48" minimum beyond the arc of the door? (Doors may swing into the clear floor space or clearance required for any fixture). 11B-603.2.3 Exception 2, 11B-305.3			Yes ☐ No ☐ N/A ■
16.42	WC Location	Is the centerline of the WC 17" minimum to 18" maximum (17" minimum to 19" maximum for ambulatory accessible WC) from a wall or partition? 11B-604.2	±18½"		Yes ☐ No ■ N/A ☐
16.43	WC Seat	Is the top of the WC seat between 17" and 19" AFF? 11B-604.4			Yes ■ No ☐ N/A ☐
16.44	WC Flush Controls	Are flush controls automatic or operable with one hand and located on the wide side of the WC where the clear floor space is provided and 44" maximum AFF? 11B-604.6, 11B-309			Yes ■ No ☐ N/A ☐
16.45	Toilet Paper Dispenser	Is the toilet paper between 7" minimum and 9" maximum in front of the WC measured to the centerline of the dispenser and centered at least 19" minimum AFF below the grab bar? 11B-604.7, 11B-309.4, Fig 11B-604.7	±4½"		Yes ☐ No ■ N/A ☐
16.46	Toilet Paper Dispenser	Is the toilet paper dispenser mounted below the side grab bar? 11B-607.7, Figure 11B-604.7			Yes ■ No ☐ N/A ☐
16.47	Toilet Paper Dispenser	Does the toilet paper dispenser allow continuous paper delivery? 11B-604.7			Yes ■ No ☐ N/A ☐
16.48	Seat Cover Dispenser	Is the highest operable part of the seat cover dispenser no higher than 40 inches AFF? 11B-603.5	±42"		Yes ☐ No ■ N/A ☐
16.49	Grab Bars	Is there a 42" side grab bar (24" minimum in front of the WC)and a 36" rear grab bar (12" minimum from CL of toilet to wall side) in the stall, 33 minimum and 36" maximum AFF measured to the top of the gripping surface? 11B-604.5.1, 11B-604.5.2, Figures 11B-604.5.1, 11B-604.5.2, 11B-604.8.1.5, 11B-609.4			Yes ■ No ☐ N/A ☐
16.50	Grab Bar Diameter	Is the outside diameter of the grab bar between 1-1/4" and 2" and 2" maximum for non-circular? 11B-609.2.1, 609.2.2			Yes ■ No ☐ N/A ☐
16.51	Grab Bar Wall Clearance	Is the space between the grab bar and the wall exactly 1-1/2 inches? 11B-609.3			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.52	Grab Bar Clearance	Is any dispenser located so that it does not obstruct the use of the grab bar (e.g., no closer than 12" above and1-1/2" below the tangent point of the grab bar unless dispenser is recess, flush with wall and has no sharp edges)? 11B-609.3	RECESSED		Yes ■ No □ N/A □
16.53	Hazards at Grab Bars	Are grab bars and adjacent walls free of sharp or abrasive elements? 11B-609.5			Yes ■ No □ N/A □
16.54	Side Grab Bar	Does the side grab bar extend at least 54" min beyond the rear wall while the other end is a maximum of 12" from the rear wall, with the front end positioned 24" min. in front of the WC? 11B-604.5.1, Figure 11B-604.5.1			Yes ■ No □ N/A □
16.55	Rear Grab Bar	Does the rear grab bar extend from the centerline of the WC 12" min. on one side and 24" min. on the other side? 11B-604.5.2, Figure 11B-604.5.2			Yes ■ No □ N/A □
16.56	Semi-Ambulant Stall	Where 6 or more toilet stalls (or combination of urinals and water closets) are provided, in addition to the 60" wide accessible stall, is at least one semi-ambulant stall 35"-37"wide with an outward swinging, self-closing door provided? 11B-213.3.1, 11B-604.8.2			Yes □ No □ N/A ■
16.57	Semi-Ambulant Stall	Are there two side grab bars in the semi-ambulant stall, 42" in length, and located 12" maximum from the rear wall? 11B-604.8.2.3, 11B-604.5.1			Yes □ No □ N/A ■
16.58	Urinals	Where urinals are provided, does at least one comply with the requirements below? 11B-605			Yes □ No □ N/A ■
16.59	Urinal Rim Height	Does the urinal have an elongated rim projecting at least 13 1/2" from the wall and a maximum of 17" AFF? 11B-605.2, Figure 11-B-605.2			Yes □ No □ N/A ■
16.60	Clear Floor Space at Urinal	Is there a clear floor space at least 30" x 48" which allows a forward approach to the urinal? 11B-605.3, 11B-305			Yes □ No □ N/A ■
16.61	Width Between Screens at Urinal	If urinal screens are provided and they extend 24" or less, is there at least 30" between the two panels? 11B-305.5			Yes □ No □ N/A ■
16.62	Width Between Screens at Urinal	If urinal screens are provided and they extend more than 24", is there at least 36" between the two panels? 11B-305.7.1			Yes □ No □ N/A ■
16.63	Lavatories	If lavatories are provided, does at least one lavatory meet the requirements below? 11B-213.3.4, 11B-606			Yes □ No ■ N/A □
16.64	Lavatory Rim Height	Is the lavatory rim or counter surface no higher than 34" AFF? 11B-606.3	RIM >34"		Yes □ No ■ N/A □

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.65	Clear Floor space at Lavatory	Is there a clear floor space at least 30" x 48" in front of the lavatory allowing a forward approach? 11B-606.2, 11B-305			Yes ■ No ☐ N/A ☐
16.66	Lavatory Knee Clearance	Is there space below the lavatory 27"high minimum AFF at a depth of 8" minimum increasing to 29" high minimum at the front edge of the counter or the front edge of the wall-mounted lavatory? Between 9" and 27" AFF, the knee clearance can be reduced at a rate of 1" in depth for each 6" in height. 11B-306.3.3 exception 1, 11B-306.3.4, Figure 11B-306.3	27 13/16" @ FRONT EDGE OF COUNTER		Yes ☐ No ■ N/A ☐
16.67	Lavatory Toe Clearance	Does the toe clearance extend 19" minimum and 25" maximum and is it 30" wide minimum? 11B-306.2			Yes ■ No ☐ N/A ☐
16.68	Lavatory Wall Projection	Does the front edge of the lavatory project a maximum of 25" at 9" AFF? 11B-306.3.2			Yes ■ No ☐ N/A ☐
16.69	Side Clearance at Lavatory	Is there a minimum of 18" from the centerline of the lavatory to the nearest sidewall or partition? 11B-606.6			Yes ■ No ☐ N/A ☐
16.70	Pipe Insulation at Lavatory	Are water supply and drainpipes insulated to protect against contact? 11B-606.5			Yes ☐ No ■ N/A ☐
16.71	Smooth Surfaces at Lavatory	Is the area below the lavatory free of sharp or abrasive surfaces? 11B-606.5	HOSE BIBB		Yes ☐ No ■ N/A ☐
16.72	Faucet Operation at Lavatory	Can the faucet be operated with one hand without tight grasping, pinching, or twisting of the wrist with 5 lbs. maximum to activate operable parts? 11B-606.4, 11B-309			Yes ■ No ☐ N/A ☐
16.73	Faucet Operation at Lavatory	If the valve is self-closing, does it remain open for at least 10 seconds? 11B-606.4			Yes ☐ No ☐ N/A ■
16.74	Mirrors	Where mirrors are provided, does at least one mirror have the bottom edge of the reflecting surface no higher than 40" AFF if located above sink or countertop? If not above sink or countertop, is the bottom edge of the reflecting surface no higher than 35" AFF? 11B-203.3.5, 11B-603.3			Yes ■ No ☐ N/A ☐
16.75	Coat Hook	Where a coat hook is provided in an accessible stall is it 48" maximum AFF? 11B-213.3.7, 11B-604.8.3, 11B-308			Yes ■ No ☐ N/A ☐
16.76	Dispensers Operating Height	Is at least one of each dispenser type accessible and is the highest operable part no higher than 40" AFF? (Indicate type, e.g., paper towel dispenser [PTD], electrical dryer [ED], soap dispenser [SD], and height in inches.) 11B-603.5			Yes ■ No ☐ N/A ☐
16.77	Floor Space at Dispensers	Is there a clear floor space at least 30" x 48" in front of the dispenser allowing either a forward or a parallel approach to the dispenser? 11B-309.2, 11B-305			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
16.78	Dispenser Operation	Can the dispenser be operated with one hand without tight grasping, pinching, or twisting of the wrist? 11B-309.4			Yes ■ No ☐ N/A ☐
16.79	Alarm	In buildings where an emergency warning system is required, is there a visual alarm (strobe) in the toilet room? 907.5.2.3, 11B-215			Yes ☐ No ☐ N/A ■
16.80	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ☐ N/A ■

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below:

- ✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities



RESTROOMS NTS





(TR2) WOMEN'S RESTROOM

(TR2) WOMEN'S RESTROOM

(TR2) WOMEN'S RESTROOM

(TR2) WOMEN'S RESTROOM

ASSEMBLY AREAS **Summary Sheet H**

Facility
Name: DEPARTMENT OF REHABILITATION

RESD
Project No.: 139602

Assembly Use Areas:
An assembly area is defined as a room or space accommodating a group of individuals for recreational, educational, political, social, or amusement purposes, or for the consumption of food and drink, including conference and meeting rooms, stadiums, grandstands, bleachers, athletic pavilions, gymnasiums and miscellaneous sport-related facilities, auditoriums, assembly halls, theaters and related facilities, such as stages, enclosed and unenclosed platforms, and orchestra pits.

Assembly use areas must comply with general accessibility requirements.

Use Survey Form 15A for rooms with fixed seating and large assembly areas, and Form 15B for smaller meeting and conference rooms up to 750 square feet in size.

List all assembly use areas in the following table and survey each of these areas with a separate copy of Survey Form 15A or 15B - Small or Large Assembly Areas. If you encounter doors, gates, signage, alarms, ramps, stairs, lifts, public telephones, or drinking fountains, survey that element with its specific survey form:

ID	Name/location/function of assembly area (or key number on site plan)	15A or 15B	Room No.	On floor
AA1	CONFERENCE/JOB CLUB	15B	117	
AA2				
AA3				
AA4				
AA5				
AA6				
AA7				
AA8				
AA9				
AA10				
AA11				
AA12				
AA13				
AA14				
AA15				

*Indicate the number of Survey Forms attached to Summary Sheet H in the **No**. field.*

Form	Item	No.		Form	Item	No.		Form	Item	No.
SF5	Drinking Fountains			SF6	Telephones			SF7	Ramps	
SF8	Stairs			SF9	Platform Lifts			SF10	Entrances and Exits	
SF11	Doors and Gates			SF12	Lobbies and Corridors			SF15A	Large Assembly Areas	
SF15B	Small Assembly Areas	1		SF19	Signage			SF20	Alarms	

SMALL ASSEMBLY AREAS

Survey Form 15B

Space/Room Item Name: CONFERENCE/JOB CLUB | Item No.: AA1 | Floor No.: | Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
15.1B	Accessible Route	Is there an accessible route of travel connecting the small assembly area to an accessible entrance within the building? (If the building or facility does not have any small assembly areas, conference or meeting rooms note so on Summary Sheet "H" and do not fill out Survey Form 15B) 11B-206, 11B-402	ROUTE HAS PORTIONS @ DOORS THAT ARE NOT ACCESSIBLE		Yes ☐ No ■ N/A ☐
15.2B	Clear Door Opening	When the door is open 90 degrees, is there a clear opening width at least 32" measured between the face of the door and the doorstop on the latch side? Are projections into the clear opening width between 34" and 80" AFF not exceeding 4"? 11B-404.2.3, 11B-404.3.1			Yes ■ No ☐ N/A ☐
15.3B	Door Maneuvering Space	If the door is not automatic or power assisted, does it have maneuvering space relative to the direction of approach as shown in CBC Table 11B-404.2.4.1?			Yes ☐ No ■ N/A ☐

Approach	*Side*	*Perpendicular to Door*	*Parallel to Door (beyond latch side unless noted)*
Front	Pull	60"	18"*****
Front	Push	48"	0"*
Hinge	Pull	60"	36"
Hinge	Push	44"**	22"***
Latch	Pull	60"****	24"
Latch	Push	44"****	24"

* Add 12" if closer and latch are provided.
** Add 4" if closer and latch are provided.
*** Beyond hinge side.
**** Add 4" if closer is provided.
***** Add 6" at exterior side of exterior doors.

11B-404.2.4, Fig. 11B-404.2.4.1

15.4B	Door Hardware	Are all handles, locks, and latches or other operative devices operable with one hand? 11B-309.4, 11B-404.2.7			Yes ■ No ☐ N/A ☐
15.5B	Door Operating Effort	Is the force required to operate a door no greater than 5 lbs? (Fire doors may have up to 15 lbs to achieve positive latching). 11B-404.2.9			Yes ■ No ☐ N/A ☐
15.6B	Other Door Requirements	Does the door comply with all applicable requirements of Survey Form 11 - Doors and Gates? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 11 for this interior accessible route. 11B-206.4, 11B-206.5, 11B-404	11.6 11.19 11.27		Yes ☐ No ■ N/A ☐
15.5B	Room/Space Identification Signs	If there is a sign designating the permanent room or space, does it comply with the requirements below? 11B-216.1, 11B-216.2, 11B-703.1			Yes ☐ No ■ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
15.6B	Tactile Exit Signs	At each exit access door from an interior room or area that is required to have a visual exit sign, is there a tactile/Braille exit sign with the words "EXIT ROUTE" mounted on the wall adjacent to the latch side of the door? 4.1.3(16); 4.30.1 /// 1011.4 item 4			Yes ☐ No ☐ N/A ■
15.7B	Side of Doors	Are permanent identification signs located on the approach side of the door as one enters the room or space? Are exit signs located on the approach side of the door as one exits the room or space? 11B-216.2, 11B-216.4, 11B-703.4.2			Yes ■ No ☐ N/A ☐
15.8B	Mounting Location	Are tactile signs mounted on the wall adjacent to the latch side of the door 48" min from baseline of lowest Braille to 60" max AFF from baseline of highest line of raised characters? For double doors with one active leaf, is the sign located on the inactive leaf? For double doors with both active leafs, is the sign located to the right of the right hand door? If there is no wall space, is the sign located at the latch side of a single door or at the right side of double door on the nearest adjacent wall? 11B-703.4.1 Figure 11B-703.4.1, 11B-703.4.2			Yes ☐ No ■ N/A ☐
15.9B	Approach	Is there a clear floor space of 18"min x 18"min, centered on the tactile characters, beyond the arc of any door swing between the closed position and 45 degree open position? 11B-703.4.2			Yes ■ No ☐ N/A ☐
15.10B	Raised and Braille Characters	Are the characters on tactile signs accompanied by Grade 2 Braille? Are the Braille dots domed or rounded shape and is the Braille placed a min. of 3/8" and a max. of 1/2" below the tactile characters, flush left or centered and 3/8" minimum from raised borders and decorative elements? If the tactile text is multi-lined, is all Braille placed together below all lines of tactile text? Are the dots within each Braille cell 1/10" o.c.? 11B-703.3, 11B-703.3.1, 11B-703.3.2, Table 11B-703.3.1	BRAILLE IS NOT GRADE 2		Yes ☐ No ■ N/A ☐
15.11B	Character Size	Are the raised characters on tactile signs between 5/8" and 2" high, uppercase letter "O" 60% minimum and 110% maximum of the height of uppercase letter "I", stroke thickness of uppercase letter "I" shall be 15% maximum of the height of the character and raised at least 1/32"? 11B-703.2.1, 11B-703.2.4, 11B-703.2.5, 11B-703.2.6			Yes ■ No ☐ N/A ☐
15.12B	Upper Case	Are the raised characters on tactile signs upper case, and sans serif or simple serif? 11B-703.2.2, 11B-703.2.3			Yes ■ No ☐ N/A ☐
15.13B	Contrast	Do the characters on signs and/or pictograms contrast with their background (light-on-dark or dark-on-light) and do the signs have a non-glare finish? 11B-703.5.1, 11B-703.6.2, 11B-7.1			Yes ■ No ☐ N/A ☐

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

SMALL ASSEMBLY AREAS

Survey Form 15B

Space/Room Item Name: CONFERENCE / JOB CLUB	Item No.: AA1	Floor No.:	Project No.: 139602

Item No.	Specific Item	Technical Requirements ADA Standards /// CBC Sections	As-built Dimensions or Survey Comments	Lessor/Architect Comments	Check
15.14B	Other Identification Signage Requirements	Does the sign comply with all applicable requirements of Survey Form 19 - Signage? If not, check the "No" field and enter all non-complying item numbers in the comment field (to the right of this box). This will eliminate the need to fill out Form 19 for this entrance. 11B-703	19.12 19.14		Yes ☐ No ■ N/A ☐
15.15B	Assistive Listening Systems (ALS)	Is there an assistive listening system provided for use in this room (assembly areas, including conference and meeting rooms) (either portable or permanently installed) and is there signage stating "Assistive-listening System Available" installed to notify potential users of the availability of such a system? 11B-216.10, 11B-219.2, 11B-703.2.4			Yes ☐ No ■ N/A ☐
15.16B	Alarms	If emergency warning systems are provided, do they include both audible alarms and visual alarms complying with Survey Form 20 - Alarms? 907.5.2.1, 907.5.2.3, 11B-215			Yes ☐ No ☐ N/A ■
15.17B	Other	If you have identified any other related barriers that were not covered by this survey form, check the "No" field and provide that information below.			Yes ☐ No ■ N/A ☐

Use this Survey Form in conjunction with the Minimum Requirements Summary Sheets and with the 2010 Americans with Disabilities Act Standards for Accessible Design (ADA Standards), and Part 2 of Title 24 of the California Code of Regulations (CBC).

Add a quick layout sketch of the surveyed area and any additional comments below

✓ SEE THE ATTACHED SHEETS FOR PICTURES OF THE AREA(S) SURVEYED

- HANDOUTS ON TOP OF BOOK CASE REQUIRE AN OBSTRUCTED REACH OVER 34" ABOVE THE FINISHED FLOOR (BOOK CASE TOP).

- CONFERENCE TABLE DOES NOT HAVE A SPACE WITH REQUIRED KNEE CLEARANCE.

RESD © 2013 v.2 Access Compliance Facility Survey Checklist for State Leased Facilities

DEPARTMENT OF REHABILITATION – 4930 W KAWEAH COURT SUITE 100, VISALIA, CA 93277



FLOOR PLAN NTS



(AA1) CONFERENCE/JOB CLUB



(AA1) CONFERENCE/JOB CLUB